

Field notes of Road Survey No 384, for Umatilla County Oregon
I met Harry Frayer, A.M. Elam and Geo. Distaven,
viewers on road No. 384., at Milton Oregon, Feby 24th 1892,
and administer usual road viewers oath to each.

We called E.R. Johnson and J.C. Hill to chain and
mark each of whom was duly sworn.

I commence at cor. to Secs. 15-16-21-22 3.6 N.R. 35 E.
and run on true line bet Secs. 21+22 Va. 21° 30' E

Decend gently.

South

- 19.70 Brook 17 lks. Wide runs west.
- 20.40 Initial post in Road no. 325 Thence along Road in land
- 20.67 Brook 17 lks. Wide runs west
- 56.70 " 12 " " " "
- 80.18 The cor. to Secs 21-22-27-28.

I repair mound around said initial post, and from a
point on true sec. line 36 lks N.E. I run on 14 sec. line

East.

- 10.93 Set a. P. 1 in a field, south of angle in traveled road.
Turn, Thence, 75° 07' left.

N. 14° 53' E.

- 15.25 Enter deep cut = Dr. Baker's old R.R. bed. (of deep cut)

- 22.57 Cut A on west side of post in fence 3 lks. E. of line. at N. end,
Turn thence 24° 30' left.

N. 2° 38' W.

- 31.36 Intersect line bet Secs. 15 + 22 - Set a. p. 3 against fence
E + W. and 27 links N. of line - Turn thence.

East

- 59.65 Center of Creek 35 lks. Wide runs N.
- 59.75 The 14 Sec. cor. bet. Secs. 15+22 in the bush on E. bank of creek.
- 80.00 Set 1 M. p. 30 lks. N. of line.

- 17.34 The Cor. to Secs. 14-15-22-23 - Intersect County road,
no. 302. Set terminus 25 lks. S.W. of Sec. Cor.

All the posts are of size, and marked and set in
mounds as required by law.

I hereby certify that the foregoing are the correct
field notes of the survey of road No. 384, which is also
a survey of Road no. 325 for Umatilla County, Oregon.
Jno. C. Arnold, County Surveyor.

Filed mch 12. 1892.
W.M. Pierce }
Clerk }

ging out
west cor
67 north
meridian
road bed
on line
(22) thence
only two
on the
county.

of Oregon
appointed
a follow-
Honorable
wayor, at
him, each,
discharge

man
Mark
corn. We
no 384
oute prac-
ears to be
ters in
and kept
led at this
said road
this 25"

urvey No 384