

Field Notes Road No 388

Field notes of Road Survey No 388 for Umatilla County Oregon
 I met Jno. B. Davidson, Jas. Hastings and N. B. Davidson
 Viewers on Road Survey No 388, for Umatilla County, Or.
 at Res. of H. Millikin June 1st 1892. We call J. C. Hill
 and Hardy E. Hamm to chm. and Wm. J. Parks to mkr.
 after qualifying each Viewer and assistant according
 to law. Under direction of said Viewers I proceed to the
 survey of road no. 388, as described in the following.
 Field Notes:—

Set initial post 45 lks. E. of cor. to Secs. 19-20-29-30
 T. 4 N. R. 37 E. and from said sec. cor. I run on line bet.
 Secs. 29 + 30 - Descend - va. 22° East

Course	Distance chs	Remarks	
South	9.00	Log fence N + S	S. 51° 10' E.
	10.00	angle post 10 on R. no. 389.	S. 85° 50' E
	15.75	Dry bed of Crank 10 lks wide, runs west, ascend through dense brush and timber	S. 6° 40' E
	20.00	R. 85° 00' Set angle post mkd. ↑	
S 85° 00' W	32.50	Leave dense brush.	S. 71° 25' W.
	36.50	Enter " "	S. 14° 55' W
S 73° 45' W	46.50	2 11° 15' Set a. p. mkd. 2	
	50.50	Swamp 100 lks wide N.W. + S.E.	
South	60.56	2 73° 45' " " " " 3 W. of line of fencing N + S. said to be on line N + S through center of Sec. 30 as established by Mr. Wilson of W. W.	S. 15° 00' E. S. 46° 15' E. South
	74.13	Thence on center sec. line N + S through Sec 30 a post 4 x 4 x 3 1/2 above ground, purporting to be center sec. 30 T. 4 N. R. 37 E.	S. 70° 20' W. S. 38° 05' E
S 41° 06' E.	77.50	2 41° 06' A tamarack 3 ins. dia. on line. mkd. 4	South
	80.00	Set post on line, and cut 5 on fir tree 3 1/2 lks. E. of line for 1 mile post	
S. 39° 00' W.	0.80	R 80° 06' Set a. p. on line, and cut 5 on fir tree 19 lks. E. of line.	
South	3.50	2 39° 00' " " mkd 6 west of line 8 lks. dist.	
	4.50	On center sec. line,	
	15.62	Summit - Descend. a post 3 x 3 ins, 4 ft. long in a md. of stone 2 ft. base x 1 ft. high, purporting to be 1/16 sec. Cor. on S 1/2 of N. + S. center line in Sec. 30	
	22.05	Brook 5 lks. wide runs west - ascend.	
	30.75	Post on line, set by former parties	
	33.15	Wagon Road bears N.E. + S.W.	
	35.75	The 1/4 Sec. Cor. bet Secs. 30 + 31, on line. Thence on N. + S. center Sec. 31.	

Course
 South
 Dist
 chs
 57
 59
 18
 8