

Field Notes of Road Survey No. 402 for Umatilla Co. Oregon.

I must have seen Sam J. Phillips and Wm A. Clark Viewers on road survey No 402 for Umatilla Co. Or. at Rio of Saml J. Phillips Oct 26. 1892 and Qualify each according to law we call Saml J. Phillips and H. M. Ritter to Chain and mark who likewise Qualify, after which under the direction of said Viewers, I find the 14 Sec. Cor. bet Secs 30 + 31 T. 4 NR 37 E. for initial point in Road Survey No 402 and set initial post sawed fir 4x4x4 mks 0 on S, and R 402 on E. S. 35° E. 37 ft dist. From said initial point I run East Va. 21° ascending gently through brush and timber,

400' Summit + 425' Descent + 705' Old Road N.W. + S.E.

750' Swag. Course N. + 1200' Ravine, course N. ascend gently

2250' Summit level brush + 2400' ascent.

2636' Cor. to Secs 29-30-31-32 on N. hill side, on line.

3200' Close for the day Oct 26th 1892.

3940' Int N+S line about 75 ft S of spruce 10 ins dia, blzd. N.W. S.W. S.W. + N.W. I cut into N.E. blzd and find mks 2x9

3985' I cut 3985 on S side of fir 12 ins. dia, on line, notched

4215' Old road bears N.E. + S.W.

4710' Int. traveled road, Course N.E. + S.W.

5270' Int N+S line 22 feet South of 14 sec. cor. bet. Secs 29 + 32, which I find in need of repairing. I set stone and make new bracing trees, as per notes on file in my office, and cut R. 402 on W. side of S.W. bracing tree, for terminal post in road survey No 402 The initial post was set in an earth mound 4 ft. sq. at base and 2 ft high. Oct 27th 1892.

I hereby certify that the foregoing notes of Road Survey No. 402 for Umatilla Co., Oregon, are correct.

Jno. C. Arnold.
County Surveyor.

Filed Nov 9-1892

W. M. Pierce

Clark