

Field Notes of Road Survey No 381 for Umatilla County Oregon
 J. Mast R. McDonald and James Rippey at Ukiah and sworn
 them in as Viewers on Road Survey No 381 for Umatilla
 County Oregon - Calling to our aid Suitable assistants of whom
 Arthur Moore and James J. Huston were sworn as chmn and H.M.
 Ritner as marker. Under the direction of said Viewers I proceed
 to the survey of Road No 381.

I commence at a post, set in a former survey of this
 road by Sa. J. Knight, Surveyor, which post is a split Laminack
 4 1/2 x 5 x 6 - 2' high marked R on E. and in md of Eeach
 1 1/2 ft base by 10 ins high in the center of Well street in the
 town of Ukiah, Or. and about 300 ft N.W of the center of Sec 14
 T5 S. R. 31 E. - I repair md leaving it 4 1/2 ft base and 2 ft high
 and cut 381 on West side of Initial post.

From which I run:

Course	Dist	Turn	Remarks
East	8.50	L. 32° 20'	Set angle Post mks 1
N. 57° 40' E	33.65	L. 12° 42'	" A. P. mks 2 in traveled Road
N. 44° 58' E	40.25	R. 72° 06'	" " " 3 at intersection of old Road to Jno Day River
S. 62° 56' E	42.77	R. 43.14	" " " 4 Thence along old Jno Day Wagon Road
S. 19° 42' E	43.00		N. Side of Canvas Creek
	46.13		S. " " " " " " " " " " " "
	49.00		Bridges in two places about 50 lks. below span in winter Dry channel 50 lks wide runs S. W.
S 6. 46 E	53.53	R. 14° 56'	Set A. P. mks 5 on E side of lane
	56.00		Center of dry channel 200 lks wide runs S. W.
	59.25		" " " " " " " " " " " "
	60.26	R. 12° 25'	Set a. P. mks 6 on West side of lane
	74.00		Center of swamp 20 lks wide runs west.
	80.00		Set 1 M. P. 45 lks. west of line against fence on West side of lane.
N. 89° 29' E	3.75	L. 96° 10'	Set a. p. mks 7 leave Jno. Day Road.
N. 0° 37' W	25.33	L. 90° 06'	" " " 8 Cor. of E. B. Gambro's preemption
N. 89° 57' E	45.40	R. 90° 34'	" " " 9 Int. traveled road Course E + W.
	65.34		Cor fence S + W
	80.00		Set 2 M. P. post
			June 29 1892.
N. 89° 57' E	6.94	R. 61° 14'	Set A. P. mks 10 at Cor fence W + S
S. 25° 49' E	10.50		Dry channel 50 lks wide runs S. W.
N. 61° 43' E	11.75	L. 69° 28'	" " " 11 at Cor fence N + E on S side of trav R along fence ascending
	14.00	L. 31° 26'	" " " 12 against fence on S. Side of trav R
N. 49° 17' E	17.85	R. 42° 15'	" " " 13 on Summit N side of trav R

558° 26 E 27.50
 60.00
 N 89° 13 E 27.70
 S. 0° 40 E. 30.50
 62.60
 65.75
 75.50
 79.25
 80.00
 2.10
 10.66
 11.50
 13.00
 14.00
 17.50
 N 88° 40 E 80.00
 7.74
 67.28
 S. 0° 47 E R
 80.00
 27.28
 N. 89° 09 E 37.25