

<p>Swan in room H.M. proceed</p>	<p>S. 85° 15' E.</p>	<p>27.50</p>	<p>22' 34"</p>	<p>along traveled road, on N of Genee The 14 Sec. Cor bet Secs. 13+18 S. S. Gambus S.W. Cor.</p>
		<p>80.00</p>		<p>3 M.P. = a basalt stone 30 x 25 x 15 ins. 30 lks. S. of line marked 111 M on N. and 15 on top = made stone md 4 1/2 ft base and 2 ft high around stone</p>
<p>this marack rch in the Sec 14 ft high</p>	<p>N. 89° 13' E.</p>	<p>27.70</p>	<p>R. 90° 07'</p>	<p>A.P. MKd 16 at 14 Sec. Cor. bet. Secs 17+18.</p>
	<p>S. 0° 40' E.</p>	<p>30.50</p>		<p>Descend gently Post Cor. to Secs</p>
		<p>67.60</p>		<p>channel on S. side of draw 15 lks Wide runs N. W.</p>
		<p>63.75</p>		<p>Main Summit</p>
		<p>75.50</p>		<p>Foot of Descent - Road N.W + S. E</p>
		<p>79.75</p>		<p>4 M.P. 30 lks, West of line marked 4 M on N. face</p>
		<p>80.00</p>		<p>Water in ravine 10 lks wide course N. W.</p>
		<p>2.10</p>		<p>Pine Creek (Dry) 40 lks wide course N. W.</p>
		<p>10.66</p>		<p>Dry channel 10 " " " "</p>
<p>River Road</p>		<p>11.50</p>		<p>70 " " " "</p>
		<p>13.00</p>		<p>Ascend bluff</p>
<p>runs whole in winter</p>		<p>14.00</p>		<p>Summit, Int. E + W line 35 lks. E. of 14 Sec. Cor. bet.</p>
		<p>27.50</p>		<p>Secs. 19 + 20 - set A.P. MKd 17 at Cor.</p>
	<p>S. 88° 40' E.</p>	<p>80.00</p>	<p>S. 90° 40'</p>	<p>Set 5 M = a stone 30 x 18 x 12 ins marked VM on N face. Set 30 lks. South of line, in open prairie, on gentle South Slope, from which a school (no house to speak of) bears N. E. about 70 chs dist. on south side of Pine Creek</p>
<p>S. W. "</p>		<p>7.74</p>	<p>R. 0° 37'</p>	<p>Old A.P. MKd 17 in Stone md = A.P. 17</p>
	<p>N. 89° 17' E.</p>	<p>67.28</p>		<p>Stone md 30 dia x 12 high purposing to be center of Sec 21. Rail fence run from this Stone</p>
		<p>80.00</p>	<p>R. 89° 56'</p>	<p>Mound, N-S-E-I set A.P. MKd 18 in this md. along line 70 ft. West of fence, course N. + S.</p>
<p>ption + W.</p>	<p>S. 0° 47' E.</p>	<p>80.00</p>		<p>Set 6 M = a basalt stone 22 x 15 x 15 ins. MKd 6 M on on E. set 45 links west of fence purposing to be on center Sec. line, made md of Stone 3 1/2 ft b x 2 ft h. around mile stone digging impracticable</p>
		<p>27.78</p>		<p>The 14 Sec. Cor. Stone bet Secs 21 + 28.</p>
<p>S. W. of low R</p>		<p>27.78</p>		<p>Set A.P. MKd 19 at stone Cor. in mouth of lane Course E.</p>
	<p>N. 89° 09' E.</p>	<p>31.75</p>	<p>S. 90° 04'</p>	<p>Cor. Set by Ra. F. Knight - leave lane - ascend center brush and timber</p>