

	45.00	Summit
	52.56	enter field of young grain belonging to Jas Banks
	64.10	beams " " " " " " " "
	69.76	The Cor. to Secs. 21-22 27-28
	R 90° 00	Set a. B. MKD 20 at Sec. Cor.
S 0° 51' E		along foot. blazed Sec line
	78.56	Wagon Road bears N 85° W + S 85° E.
	80.00	A tamarack, 30 ins, dia, bears 8 lks. West of line MKD. 7 M R 381 on E.
	77.34	The 1/4 Sec Cor. bet. Secs. 27 + 28.

June 31st or July 1st - 1892

	R 42° 34'	Set a. B. MKD 21 at 1/4 Sec. Cor.
S 41° 43' W	38.10	S. 46° 15' " " " 22 E. of cluster of large pines
S 4° 44' E.	45.97	R. 61° 50' " " " 23
S 57° 05' W.	50.85	R. 78° 40' " " " 24
S 87° 45' W.	56.00	S. 40° 06' " " " 25
S 42° 42' W.	58.00	S. 28° 30' " " " 26
S 4° 22' W.	67.97	S. 6° 38' " " " 27
S 2° 16' E.	79.10	A pine 30 ins. dia bears E. of line 11 lks. dist. MKD 8 M R 381 on W. side

	9.34	S. 8° 14' Set a. B. MKD 28
S 10° 30' E.	13.70	R. 31° 11' " " " 29
S 20° 42' W.	19.52	R. 18° 06' " " " 30
S 38° 48' W.	20.81	R. 33° 45' " " " 31
S 72° 35' W.	26.60	S. 62° 12' " " " 32
S 10° 21' W.	33.14	S. 5° 10' " " " 33
S 5° 11' W.	38.80	S. 16° 36' " " " 34
S 11° 25' E.	48.14	S. 25° 32' " " " 35
S 36° 57' E.	62.75	S. 4° 45' " " " 36
	72.77	Cut R 381 on N. side of a leaning scraggy pine 36 ins, dia. on gentle S. slope. on line.

I hereby certify that the foregoing are the correct notes to Survey of Road No 381 for Umatilla County Oregon, and that all the stakes were of legal size & marked & set in mounds as required by law.

Jno. C. Arnold,
Surveyor.

Filed July 13-1892 }
W. M. Pierce }
Clerk }