

Field Notes of Road Survey No. 400 for Unmatilla Co. Ogn.

J. J. Price and J. B. Tucker, Viewers on Road Survey No 400 for Unmatilla, duly sworn at the beginning of said road, on Aug 26<sup>th</sup> 1892 H. M. Ritter and J. C. Hill called to chain and mark who were also sworn as required by law under direction of said Viewers I set Initial post against cor fences E + S on S. side of lane Course E. and 50 links S. E. of center of Sec 27 34 N. R 36 E. W. M. from which center Cor. I run on center Sec line.

chs Va 18°30' E.

North

- 0.65 Dry Ravine Course N E ascend gently
- 1.75 2. M. P. on R. No. 330. brass 18 lks West.
- 3.10 Center garden. fences E + W.
- 5.70 Leave " " "

10:00 Summit

16:75 Set angle Post Marked 1, 3.30 chs. S of 1/16 Sec. Cor. as established by C. K Bryson and A. J. Nos et al. Thence I Turn & 57° 15'

N. 51° 15' W

18.50 Set angle post Marked 2, and turn & 14° 12'

N. 71° 27' W

24.61 " " " 3, at intersection of line

running E + W through center of NW 1/4 of Sec 27 Thence I turn on 1/4 Sec line; ascend gently.

West

32:00 Descend gently

34:25 Dry Gulch Cross N.

34:34 The 1/16 Sec Cor on W body of NW 1/4 of Sec 27 as set by owners of land affected thereby

40:00 Top of hill level

45:00 Descend gently

50:85 Dry Gulch Course N. ascend gently

54:93 The 1/16 Sec post cor on W body of Sec 27 as set by owners of land contiguous to said cor. a pine tree in NE cor of School house lot 8" dia. brass S. 38 lks dist. Marked R 400 on E. This tree has been taken for terminus of Road Survey Nos 329 + 330. All the posts are of regulation size and are marked and set in mounds as required by law.

I hereby certify that the foregoing are the correct Field notes for Road Survey No. 400. for Unmatilla County Oregon.

Jno. C. Arnold, Surveyor

Filed Sept 5- 1892 }  
W. M. Prince }  
Clerk }