

- brass right of line about 700 ft. dist.
- 1937' A basalt stone 20 x 12 x 6 ins, MKd XXIII A on E face in small md. of stone, near trav. Road. to mark angle No 13
Turn thence left 16° 21'
- 5180' Set a Basalt stone 28 x 15 x 7 ins, MKd VIII M on N. face in md of earth and stone, 4 ft. base x 20 ins. high.
30 ft. Left of line.
- 542' Set a. P. MKd. 24 Int N+S Sec line
a md of stone presumably Sec cor.
brass Right of line 71° 55'
- 989' O Same md of stone brass right 37° 54'
- 1252' Set a. P. MKd. 25 = Stake in stone md - Digging impracticable
Turn thence, Right 23° 45'
- 4148' Set a. P. MKd. 26, and turn Left 3° 40' - Enter timber.
- 4808' " " " 27 " " Right 10° 27'
- 5000' Leave timber
- 5780' Set an oval shaped boulder, 28 x 18 x 12 ins, MKd. IX M on N. face in md. of stone 2 ft. high x 4 ft. base, 105 ft. South of line.
- 791' Set a. P. MKd. 28, and turn Right 10° 35'
- 1527' " " " 29 " " Left 10° 37' - Descend to Potts
Fence N+S
- 3818' " " " 30 " " Right 7° 07' - Enter timber
- 5086' " " " 31 " " Left 87° 08'
- 5252' Cut 10 M on S. side of a Laminack tree 24 ins. dia, 9 ft. Right of line.
- 100' Foot of hill
- 200' Dry bed of creek 15 ft. wide, course N.
- 1308' Set a. P. MKd. 32, and turn Right 30° - Sharp corner 75' Left
- 1986' " " " 33 " " Right 9° 30'
- 3000' Dry water course 5' wide brass N.
- 3335' Set a. P. MKd. 34, and turn Right 35° 50'
- 3530' Dry Washout 3 W - N.
- 3885' Fence brass N+E.
- 4202' " " " 35, a pine 10 ins. dia MKd 35, on S. side brass
Right 52° 45', Dist 185 ft. Turn, thence, Right 41° 35'
- 4245' Dry Wash, 6 ft. wide, course N. E.
- 5280' Set a post about 7 ins. dia x 4 ft. long MKd 11 M on N. side.
30 ft. Left of line, in md of earth and rubbish
3 1/2 ft. base x 10 ins high - digging impracticable - material scarce
- 132' Set a. P. MKd 36 and turn Left 5° 08' - From O Right 90° Dist 6 ft.
- 1224' " " " 37 " " " 27° 07'