

Field Notes of Road Survey No 429 for Umatilla County.

I meet Westward. P. C. Costello & Jos. Sumner Viewers on road Survey No 429, and Call E. R. Thomson J. M. Reeves & F. M. Whitney to Chain mark and Flag each of whom, Viewers and Assistants duly qualify.

I commence at 36 mile post in the Town of Alba on a road survey no 275 (Pendleton to Orion City wagon Road Survey 1856. and run

Turns	Dist	Ascend	Descend.
	500		Descend ends.
L 90° 35'	1664	1	Centre tree, Mouth of lane. run'g E. (Sp 5 SR 31 E)
L 6° 42'	3650	2	" of lane. 5' E of small culvert.
L 5° 40'	4721	3	
	5277		1. m. P. a pine 2' dia. mcd 1. M on S. 12' N of line Enter scattering Timber.
R 72° 35'	1993	4	In stone md. on W hill side
L 61° 30'	2775	5	" " "
R 33° 49'	2998	6	" " "
L 103° 20'	3242	7	" " "
	3300		Descend.
R 99° 44'	3537	8	In Stone md.
	3740		Dry Gulch. ascend
L 30° 11'	3821	9	
	4370		Here be cor. bet sec's 19 & 20 Sp 4 SR 32 E
	5277		2. m. P. a stone 18x16x16 ins mcd 11 M. on N face. 8 ft. S. of line; Rod McDonalds house bears N. about 125 ft.
			Descend from Summit
	330		Little Owens Creek. runs S. bridged
R 59° 10'	430	10	thence down creek to. S.
R 15° 41'	1643	11	In Stone md.
L 31° 00'	2014	12	" " " on W hill side
R 16° 05'	2225	13	at 2. m. P. on Road Survey 271
	2690		Little Owens Creek at foot of hill, runs SE. bridged
	3240		" " " runs W.
	5280		3. m. P. a pine 30 ins dia mcd 3 M on W on line. in lane
	400		Lane runs W
	2205		the 3 m. P. on Road 271
	2800		Dixie Ranch house bears E. about 500 ft dist
	2980		Line
	4425		South Fork of Owens Creek. bridged. Ascend.