

Field Notes of Road Survey # 135 for Union County, Oregon  
 Pursuant to order of County Court for Union County, State of  
 Oregon I met Rot Rimmer and A.M. Rellum viewors on Road  
 Survey # 135 at Pendleton Oregon April 18<sup>th</sup> 1894 and administered to  
 each the usual Road viewors oath calling N. M. Perkins, Hamilton  
 to assist. I proceed, under direction of said viewors to survey said  
 Road No 135.

I cut O.R. 135 on S side of Cottonwood tree about 6 ins dia  
 at foot of steep bluff on N side of old Thomas & Ruckler grade  
 about 120 feet west of the point of intersection of said grade with  
 the E boundary of the U.S.R. line near the center of Sec 21 T3 NR 36W  
 using an old style of open sight compass adjusted to Mag,  
 var of 20° E and taking all angles with the needle, above, I run  
 from a point in said grade 10' S of tree described

|  |             |      |                                                                                                                                                                                                                                                  |
|--|-------------|------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|  | 168° 00' E  | 120' | Old fence tree, 2' dia of grade, about 36' dia repeats Res line                                                                                                                                                                                  |
|  |             | 200  | Ravine course S.                                                                                                                                                                                                                                 |
|  |             | 425  | George Muller's house about 400' R of line                                                                                                                                                                                                       |
|  | N 84° 00' E | 700  | ↑ at post in S end of bare fence 20' W of line                                                                                                                                                                                                   |
|  | N 94° 00' E | 942  | ↑ on perp face of basalt rock 9' N of line                                                                                                                                                                                                       |
|  | N 73° 00' E | 1334 | ↑ " E side of pointed basalt rock in prop bank 4' N of line                                                                                                                                                                                      |
|  | N 77° 00' E | 1522 | ↑ " face of rock in high bluff " " " " " "                                                                                                                                                                                                       |
|  |             | 1950 | C.D. Rosser house trans R of line about 200'                                                                                                                                                                                                     |
|  |             | 2224 | Waters edge in Umatilla River 83 ft on line course S.W.                                                                                                                                                                                          |
|  |             | 2307 | " " " " " opposite bank                                                                                                                                                                                                                          |
|  | N 87° 00' E | 2523 | ↑ cut on Cottonwood 3 ins dia 8 ft R of line                                                                                                                                                                                                     |
|  | N 51° 00' E | 2734 | ↑ " leaning dead tree, for, 20' R of line on steep N hill side                                                                                                                                                                                   |
|  |             | 3179 | Waters edge in Umatilla Riv 96 ft on line course W.                                                                                                                                                                                              |
|  |             | 3275 | " " " " " opposite bank                                                                                                                                                                                                                          |
|  | N 71° 30' E | 3345 | ↑ cut on dead burnt Ball 40" dia lying on line, three fawns river                                                                                                                                                                                |
|  | N 77° 34' E | 4156 | ↑ a made small stone mound on line                                                                                                                                                                                                               |
|  | N 60° 30' E | 5064 | ↑ 20 ft from waters edge on line                                                                                                                                                                                                                 |
|  |             | 5084 | Waters edge in Umatilla Riv 82 ft on line course S.W.                                                                                                                                                                                            |
|  |             | 5116 | " " " " " opposite bank                                                                                                                                                                                                                          |
|  |             | 5374 | Out line of ports course about N 50° E to S 80° W.                                                                                                                                                                                               |
|  |             |      | cut 1 M and on a basalt stone 30 x 24 x 19 ins in stone mound 14 ft R of line                                                                                                                                                                    |
|  |             |      | Note angles 7a and 7b were ordered by the viewors at request of Thomas<br>Shaw owner of lots 9-10-15-16 in Sec 22 T3 NR 36W which account<br>for the length of this mile as said angles were interpolated after<br>the survey had been completed |
|  | N 50° 30' E | 182  | ↑ on green fir post 3" dia by fence post on line <sup>Surveyor</sup>                                                                                                                                                                             |
|  | N 57° 30' E | 400  | ↑ " split " " by fence post on line                                                                                                                                                                                                              |
|  | N 52° 30' E | 525  | ↑ " green " " 3" dia dia by fence post on line, leave post line                                                                                                                                                                                  |
|  | N 42° 00' E | 650  | Thos Shaw house trans L of line about 250 ft washout, course S.W. summit of stone point                                                                                                                                                          |