

Survey
range 34
Rough
th. West
It is a
chance
1/2 mile,
feet wide.

That in our opinion the said proposed road should be established for the following reasons:

- 1st. The route is quite practicable.
- 2d. The road is much needed for an outlet to residents within its vicinity.

Dated this 29th day of May, 1894.

George DeHaven
A. M. Elam
H. L. Frazier
Viewers

Filed June 30, 1894
W. M. Purce County Clerk
By C. M. Purce, Deputy.

Field Notes of Road Survey No. 441. For Umatilla County, Oregon.

Pursuant to order, I met A. M. Elam, George DeHaven, and H. L. Frazier, the appointed board of viewers on Road Survey No. 441, for Umatilla County, Oregon, at T. Bartlett's Hotel, in Milton, said County and State, who qualify, each, as required by law. Ed. Hodgens and H. M. Ritner were called and sworn, as per law, to act as chain bearers.

Using a Polar Compass, adjusted to the suns declination for June 29, 1894, the date of meeting the said viewers, I commence at stone cor. to sees 23, 24, 25 and 26, T. C. N. R. 34 E. - setting the initial post 42 1/2 ft N. W. from said see cor., I run on line, between sees 25 and 26, said T. C.

South	1320 ft	Ret 1, and turn, thence R. 90°	ca. 21°, 30' E.
West	2640 "	" 2 " " " S. 90°	
South	3960 "	" 3 " " " R. 90°	
West	5290 "	" 4 at probable center see 26 - set 1 m pin end of earth 4 ft base x 2 ft high - fir 4" x 4", 4' long, mkd 1M on S. face, and set 30' N of line; turn thence S 41°, 30'.	
S. 48°, 30' W	32 "	Int. fence N th & S.; E. bank of ditch 18' wide, brs. N.	
	162 "	E. bank of branch of Dry Creek, 33' wide, runs N. W.	
	200 "	Ret 5 in flat, and turn thence S 25°, 15'.	
S. 23°, 15' W	410 "	E. bank of main chan. of Dry Creek 20' wide, course N. W.	
	480 "	Ret 6, and turn thence S 40°, 12'.	
S. 19°, 03' W	1134 "	" 7 " " " R. 27°, 30'.	
S. 46°, 33' W	2164 "	" 8 " " " S. 30°, 50'.	
S. 15°, 43' W	2743 "	" 9 " " " R. 13°, 10'.	
S. 28°, 53' W	3150 "	" 10 " " " S. 11°, 10'.	
S. 17°, 43' W	3492 "	" 11 " " " R. 30°, 30'.	
S. 48°, 13' W	4151 "	" 12 " " " R. 35°, 30'.	
S. 13°, 43' W	4440 "	E. bank of Pine creek, 50' on line, runs nearly N. at this pt.	

vicin
Dick
Uton,
said
ing of
pur-
tially
Ed.
ded
is near
xl.
e and
such
our
mers
ere
of said
wood,
aged
id road
ten.
ppear
herunto