

ROAD No 484

In the matter of the viewing, Surveying and Laying out County Road No 484

To the Honorable County Court of the State of Oregon for Umatilla County:

We, the undersigned viewers, heretofore appointed to view and locate Road No 484, submit the following report: Pursuant to an order of the Honorable Court we met John W Kimbrell, Surveyor, at Postoffice in Pendleton, on March 31st, 1897, and were by him each duly sworn to faithfully and impartially discharge the duties of our appointments.

We called to our aid Thomas McMahon, Ed Money, chairmen; J W Kimbrell Marker, who were by the surveyor each duly sworn. We viewed, surveyed and located said road No 484 as specified in our order and find the Route practicable and would most respectfully recommend the route be established as a public highway of Umatilla County, Oregon,

J W Kimbrell } Viewers Road Survey No 484
J W Barnhart }
J S McLeod }

Field Notes of County Road No 484

I commenced at the 1/4-section corner between Secs 14 and 15, in Township 1 South, Range 32 East of Willamette Meridian. Set stake 4 feet long and 4 inches square, 30 feet East of the initial point marked R 484. Built mound four feet wide at base and 18 inches high; dug pits N-S and East of Post.

Thence I run South between Secs 14 and 15, Var. 21° E

Course	chains	Distance	Angle	Departure
South	19.25		1	
S 21° E	16.80	36.05	2	21° S
S 25° W	13.54	49.59	3	46° R
South	30.41	80.00		25° S 1 Mile

Set post 4 feet long and 4 inches square 30 feet to the right marked 1 M. Built mound 4 feet wide at base 18 inches high, dug pits N-S, E and W

South	55.50		4	
S 45° E	4.75	60.25	5	45° L
S 38° W	5.55	65.80	6	83° R
South	14.20	80.00		38° S 1 Mile

Set post 4 feet long and 4 inches square 30 feet to the right, marked 2 M; Built mound 4 feet wide at base, 18 inches high, dug pits N and S of post

South 5.25 5.25 to the 1/4 Section corner between Sections 26 and 27 in Township 1 North, Range 32 East Willamette Meridian. Set post 4 feet long and 4 inches square, 30 feet East of Road Terminus, marked R No 484; Built mound 4 feet wide at base, 18 inches high, and dug pits South and East of post