

ROAD NO
486.

In the matter of Viewing Surveying and Laying Out County Road No 486

To the Honorable County Court of the State of Oregon, for Umatilla County:

We, the undersigned, the Viewers heretofore appointed to view and locate Road No 486, submit the following report: Pursuant to an order of the Honorable Court, we met John W Kumbrell, Surveyor, at State Line, the Commencing of Road, on April the 15th, 1897, and were by him each duly sworn to faithfully and impartially discharge the duties of our appointments.

We called to our aid J A Klieker, Thomas Craft and J W Sealf, Chairmen, J J Conrad, Marker, who were by the Surveyor each duly sworn. We viewed, surveyed and located said road No 486, as specified in our order, and find the route practicable and would most respectfully recommend the same be established and declared a public highway of Umatilla County, Oregon.

J R Livingston }
James A Pate } Viewers, Road Survey No 486
Christian Miller }

Field Notes of County Road No 486

I commenced on the State Line between Oregon and Washington at a point in Sec 18, Township 6 North, Range 38 East Mill Mer. 705 links East of the NW Corner of Lot 3 in said Sec 18

Set Stone 22x14x7 inches 20 feet West of initial point Marked A 486

Thence	Distance	Chains	Departure	Angle
S 29° E	9.10	9.10		
" S 34° E	17.78	8.68	5° E	1
" S 24° 30' E	22.78	5.00		
" S 39° 30' E	29.18	6.40		
" S 18° E	33.10	3.92		
" S 28° 30' E	35.70	2.60		
" S 63° 15' E	40.42	4.72		
" S 42° 40' E	57.30	16.97		
" S 58° 25' E	64.02	6.63		
" S 50° 35' E	69.77	5.75		
" S 62° E	80.00	10.23		1 Mile

Set Stone 20x2x7 inches 20 feet to the right, Marked L.M., also a Palm 20 inches bears S 72° W 34 links dist. Marked 1 M. 735.

Thence	Distance	Chains	Remarks
S 62° 30' E	27.05		
" S 73° 30' E	30.7	4.45	Mill Creek, 38 links across, Runs SW
" S 79° E	35.50	4.00	
" S 87° 10' E	45.0	4.50	creek 73 links wide, runs north
" S 79° "	49.08	7.58	

Field Notes
March, 1897

Plate 25 Chs. 1'