

Field Notes of Survey of Road # 527. Made July 23, 1901.  
 Beginning at a Stone the 1/4 Section Corner between Sections 17 and 18.  
 Township 5 South Range 32. E.W.M. at which point I take an  
 observation on the sun to establish true North.

Standard time 1 o'clock P.M.  
 Local time 1.04<sup>m</sup> 30<sup>s</sup> P.M.  
 Latitude 45° 09' N  
 Declination of sun 20° 06' 15" N  
 Refraction 0° 00' 34"  
 Altitude angle 62° 00'  
 Variation 19° 45' E.

20 feet south of beginning I set required post marked R. 527.  
 Thence I Run

	Left	Right			
7789' 45" E.			5269.	5269.	1/4 sec cor. E line sec 16.
North	89° 45'		11	5280.	set 1 mile Post.
			2736		Cor to sec. 8, 9, 16 and 17.
East		90°	2544	5280	set 2 mile Post
			2740		Cor to sec. 9, 10, 15 and 16.

at this point I intersect County Road and set post marked R.  
 J. 527. 20 feet to south to mark terminus of Road as per  
 instructions

I hereby certify that the foregoing is a true and correct copy  
 of the field notes of Survey of Road # 527. as made by me  
 July 23, 1901

E. E. Macomber  
 County Surveyor

ROAD No  
 Public Easement  
 Rd # 531

Field Notes of Road #  
 This Road being one of public easement no viewers were  
 appointed. = Survey made Aug 29, 1901.

Road as yet has received no number. therefore initial point  
 not marked with number at the time of survey.

Beginning at the 1/4 Corner between Sections (1) one  
 and (12) Twelve in Township (1) one South Range (32)  
 Thirty-two. E.W.M. at which point I took an observation  
 on the sun to establish true North.

Standard time 11 o'clock A.M.  
 Local time 11<sup>h</sup> 04<sup>m</sup> 30<sup>s</sup> A.M.  
 Latitude 45° 30' North  
 Declination 9° 24' 24"  
 Refraction 0° 00' 44"  
 Altitude angle 53° 00'