

Surveyor's Oath.

State of Oregon,
County of Umatilla, ss.

I, L. E. Macomber, do solemnly swear that I will support the constitution of the United States and the constitution and laws of the State of Oregon, and that I will faithfully and impartially discharge the duties of the office of Surveyor in the above intitled matter, to the best of my knowledge and ability so help me God.

L. E. Macomber.

Subscribed and sworn to before me this 17 day of Dec A.D. 1901.
A. L. Frazier
Viewer.

Field notes of Survey of change in Road #440.
Survey made Dec 17, 1901.

Beginning at the Initial point of the Original Survey of the Road #440 said point being indicated by mound of Stone and Stake 50 rods South of the $\frac{1}{4}$ Section corner on the north line of Section 22 Twp. 5 N. Range 36 E. W.M. I took a solar observation to establish true meridian.

- Standard time 1. O'clock P.M.
- Local " 1.06 " " "
- Declination of Sun $23^{\circ} 20'$
- Refraction $2' 37''$
- Altitude 21°
- Variation of needle $21^{\circ} 30'$

From Initial point of Road 440 I run

	L	R	Dist	Total dist
S $73^{\circ} 37' E.$			200.	
N $85^{\circ} 30' E.$	$20^{\circ} 53'$		192	392'
N. $68^{\circ} 58' E.$	$16^{\circ} 32'$		18'	475'

at which point I intersected line of old Survey. setting stakes at all angles. L. E. Macomber
County Surveyor.

I hereby certify that the above is a true and correct copy of the Field notes of Survey of change in Road 440 as made by me on Dec 17 1901.

L. E. Macomber
County Surveyor.

Filed this 2 day of Jan 1902

W.D. Lambrian clerk
by B.B. Hall deputy