

by reason of the location of said Road to property owners to-wit; the O R & N Co nothing, W W Whitworth nothing, Mrs Sadie Elder, nothing.

John W Kimbrell
L C Rothrock
J E Bennett

Board of County Road Viewers of Umatilla County
State of Oregon.

Filed
July 10, 1906
Frank Saling, Clerk
By R T Brown, Deputy.

FIELD NOTES OF OLD ROAD TO VACATE

COMMENCING at a point 2° E 1275 chs distant from the corner of Secs 15-16-21 & 22 in T 3 N R 29 E, also the terminus of Road No 595
Thence N 42° E 102 chs dist
N 5° W 1217 1319
North 1970 3289
N 38° W 925 4214
N 46° W 950 5164 R T at the East end of college Street in the Town of Echo in the NE1/4 of the SE1/4 of Sec 16 T 3 N R 29 E.W.M.

I hereby certify that the foregoing Field Notes of Old Road to Vacate are correct as surveyed by me on the 9th day of July 1906.
John W Kimbrell, County Surveyor
for Umatilla County, Oregon.

REPORT OF BOARD OF COUNTY ROAD VIEWERS.

In the Matter of Viewing, Surveying and Laying out County Road No-old Road To the Honorable County Court of the State of Oregon for Umatilla County.
We, the undersigned Board of County Road Viewers heretofore instructed to view, survey and locate Road No--old road submit the following report;
Pursuant to an order of the Honorable County Court we met at Office of County Surveyor in Pendleton, Oregon on the 9th day of July 1906
We called to our aid
D I Mitchell, Chairman
R E Tarbett, Chairman

who were by the Surveyor each duly sworn. We viewed, surveyed and located said Road No old road, as specified in our order. We find said route needed for use of the construction of the Government East Umatilla Irrigation Canal and is unnecessary for the use as a public highway, we would therefore most respectfully recommend the same be vacated and abandoned as a public highway of Umatilla County, Oregon.

John W Kimbrell
L C Rothrock
J E Bennett

Board of County Road Viewers of Umatilla County State of Oregon.

Filed July 10, 1906
Frank Saling, Clerk
By R T Brown, Deputy.
Approved July 13, 1906
T P Gilliland, County Judge
Horace Walker, Co. Comm
H B Lee, County Comm.

Field Note of Road No. 596.

Commencing at the NW Corner of Sec. 9 T 3 N R 29 E.W.M Set Post 30 feet west of the Initial point marked R 596 dug pits and raised mound of earth 18 ins. high 4 feet wide at base; thence I run North between Secs. 4 and 9 a distance of 40°° chains along County Road No. 477 to the 1/4 Sec. Corner bet Secs 4 and 5 in T 3 N R 29 E.W.M.; thence North bet said Secs. 4 and 5.
8000 set post 30 feet to the left Marked 1 M dug pits and raised mound 18 ins high 4 ft wide at Base thence North bet Secs 32 and 33
7625 Irrigation ditch 20 feet wide thence West
7525 the corner of Secs. 28-29-32 & 33
8000 set post 30 feet to the left marked 2.M. dug pits and raised mound 18 ins high 4 ft wide at base thence North bet Secs. 28 & 29
7800 the Corner to Secs 20-21-28&29
8000 set post 30 feet to the left Marked 3 M. dug pits and raised mound 18 ins high 4 ft wide at base; thence North bet Secs 20 and 21
7775 the corner to secs 16-17-20 & 21
8000 set post 30 feet to the left marked 4M dug pits and raised mound 18 ins high 4 ft wide at base; thence North bet Secs 16 and 17
7750 the cor to secs 8-9-16 and 17
8000 set post 30 feet to the left Marked 5 M dug pits and raised mound 18ins high 4 ft wide at base; thence North bet Secs 8 & 9
1825 Irrigation ditch 12 ft wide E & W
7750 the corner to secs 4-5-8 & 9
8000 set post 30 ft to the left marked 6 M dug pits and raised mound 18 ins high 4 ft wide at base; thence North bet Secs 4 & 5
8650 Irrigation ditch 8 ft wide N 6
8000 the closing corner to secs 4 & 5 on first standard paralel North between Tps 4 and 5 N. R. 29 E. W. M.