

Report of Board)
 of) In the matter of viewing, surveying and laying out County
 County Road Viewers) Road No. 718

To the honorable county court of the State of Oregon, for Umatilla County.
 We, the undersigned board of county Road viewers, heretofore instructed to view, survey and locate Road No. 718, submit the following report:
 Pursuant to an order of the honorable County Court, we met at the commencing point of said road, on the 30th day of June, 1911.
 We called to our aid

W.J. Stockman Chairman
 L.C. Rothrock Chainman
 J.W. Kimbrell Marker

Who were by the surveyor each duly sworn. We viewed, surveyed and located said road no. 718 as specified in our order. We find said route. Practicable and would most respectfully recommend the same be established and declared a public highway, of Umatilla County, Oregon. The cost of construction will be about \$50.00
 The damage to be sustained by property owners, by reason of the location will be nothing.

Board of County Road Viewers of (John W. Kimbrell Deputy
 Umatilla County, State of Oregon. (W.J. Stockman
 (L.C. Rothrock.

Field Notes of Road No. 718.

Commencing at the S.E. Corner of the S.W. 1/4 of the S.W. - of section 13, in T. 6, N.R. 35, E.W.M., set marked R. 718 made mound 18" high 4' wide at base.
 Thence North 52.53 chains to the State line. between the State of Oregon and Washington at a point 2336 feet East of the N.W. Fractional Corner of said Section 13, Set post marked R.T. No. 718 made mound 18" high 4' wide at base.
 I hereby certify that the foregoing Field Notes of Road No. 718 are correct as surveyed by me on the 30th day of June 1911.

Geary Kimbrell, County Surveyor.

Filed July, 5th, 1911
 Frank SalinG. Clerk.

AMENDED REPORT

IN THE MATTER OF VIEWING SURVEYING AND LAYING OUT
 COUNTY ROAD NO. 712.

To the honorable county Court of the State of Oregon for Umatilla County,
 An error having appeared in the plat and field notes of the original report of County road No. 712, which was prepared by me, I beg to submit the herewith plat and field notes in order to correct said error.

The said original plat and field notes does not include a mile of road, which was petitioned for, as follows: beginning at the N.W. corner of Sec. 7 T. 4, N. R. 28 E.W.M. and extending south along the west boundary of said Sec. 7. to the S.W. Corner of said Sec. 7.

The route is most practicable, the cost of construction will be nothing in addition to that estimated in the original report and the damage to be sustained by property owners will be nothing.

The original plat and field notes of the report of the board of county Road viewers, in the matter of viewing, surveying and laying out of County road No. 712 should be as per plat and field notes herewith submitted

Respectfully submitted,
 Geary Kimbrell, County Surveyor.

Amended Field Notes of County Road No. 512.

I commence at the 1/4 Sec. corner on the N. side of Sec, 5 T. 4, N.R. 28, E.W.M.
 At a point 20 ft. S. & 20 ft. W. of aforesaid point I set a post, 4 ft. long, 4 ins. square, marked R. 712: dug pits, 18 X 18X 12 ins N & S of post, and raised mound of earth 18 ins high 4 ft. base, around post. Thence following the subdivisional section line south 80.00 chs. to a point from which I set, to the right, 20 ft. distant, a post; 4 ft. long, 4 ins. square, marked 1 M: dug pits, 18X 18X 12 ins., N.&S. of post, and raised mound of earth, 18 ins, high, 4ft. base around post.

Thence south 1.10 chs. to the 1/4 sec. corner between secs. 5&8 angle 1. thence west 78.90 chs. to a point from which I set to the right, 20 ft. distant, a post 4 ft. long 4 ins. square. marked 2 M; dug pits, 18 X 18 X 12 ins., N.&S. of post, and raised mound of earth 18 ins. high 4 ft. base around post. Thence west 7.60 chs to irrigation canal 25 lks. wide course north. Thence West 30.34 chs. to the N.W. corner of sec. 7 in said township and range, angle 2; Thence south 22.40 chs. to irrigation canal 25 lks wide course N.E. thence south 19.76 chs. to a point from which I set the the right. 20 ft. distant, a post 4 ft. long, 4 ins. square, marked 3M: dug pits, 18x18x12 ins N.&S. of post raised Mound of earth, 18 ins, high, 4 ft. base, around post.

Thence south 39.88 chs. to the S.W. corner of sec 7 in said township and range from which I set, 20 ft. N. & 20 ft. E. a post, 4 ft. long 4 ins square, marked R.T. 712: dug pits E.&W. of post, and raised a mound of earth, 18ins high, 4 ft. base around post.

I hereby certify that the foregoing field notes of County Road No. 712 are correct as corring to survey thereof, commenced on the 23 d day of may, 1911.
 Geary Kimbrell
 Surveyor for Umatilla County, Oregon.

Filed July 6, 1911
 Frank SalinG, Clerk.

Correction approved this 5th day of July 1911.
 J. W. Maloney, County Judge.
 M. Colburn } Co. Comm.
 Horace Walker }