

FIELD NOTES OF ROAD NO. 768

Commencing at the N.W. Corner of the S W $\frac{1}{4}$ of the SW $\frac{1}{4}$ of Section 33, T. 5 N.W. 29 E.W.M. Set post $\frac{1}{2}$ ins. square $3\frac{1}{2}$ feet long 35 feet N.E. from initial point marked P. No. 768 dug pits N & E and raised mound $\frac{1}{2}$ feet at Base 18 ins high around post, thence East through center of the S $\frac{1}{4}$ of Section 33 80.00 chs Set post $\frac{1}{2}$ ins square $3\frac{1}{2}$ feet long 35 feet N.W. Marked 1, M Dug pits and raised mound $\frac{1}{2}$ feet Base 18 ins high around post. Thence East 3.78 Ditch Course N.E. 8 feet wide.

59.81 Chains to the West edge of the Government Reservoir Set post $\frac{1}{2}$ ins square $3\frac{1}{2}$ feet long marked P T No. 768 Dug pits N & S and raised mound $\frac{1}{2}$ feet at base 18 ins high around post.

I hereby certify that the foregoing field Notes of Road No. 768 are correct as surveyed by me on the 19th day of Oct. 1914.

Geary Kimbrell County Surveyor, by John W. Kimbrell Deputy

REPORT OF BOARD OF COUNTY ROAD VIEWERS.

In the Matter of viewing, surveying and laying out County Road No. 768.

To the Honorable County Court of the State of Oregon, for Umatilla County.

We, the undersigned Board of County Road Viewers, heretofore instructed to view, survey and locate Road No. 768 submit the following report:

Pursuant to an order of the Honorable County Court, we met at Pendleton, Oregon, on the 19th day of October, 1914

We called to our Aid.

W.J. Stockmen Chairman
L.C. Rothrock Chairman
J.A. Reed, Flagman
J.W. Kimbrell Marker

who were by the Surveyor each duly sworn. We viewed, surveyed, and located said Road No. 768 as specified in our order. We find said route practical and most respectfully recommend the same be established as a public highway of Umatilla County, Oregon. The cost of construction will be about \$50.00. The damage to be sustained to property owners by reason of the location of said road will be nothing.

John W. Kimbrell
W.J. Stockmen
L.C. Rothrock
Board of County Road Viewers of
Umatilla County, State of Oregon.

Filed Oct. 24th, 1914
Frank Saling, Clerk
By R.T. Brown, Deputy

Approved and road ordered opened this 5th day of Nov. 1914

J.W. Maloney, County Judge
H.A. Waterman, County Com
H.M. Cockburn, County Com.

NOTES OF SURVEY OF ROAD NO. 770

Feb. 20-24-25-1915

To the Honorable County Court, Umatilla County Oregon.

I submit the following as the notes of the survey of Road No. 771. Began at a stone marked "R" which is 231 feet North of the $\frac{1}{4}$ corner on section line between Sect's 15 & 16 T. 3 N. $^{\circ}$. 29 E.W.M. from which a fence post marked "R" 770 bears N. 68° -0' W. 7.55 feet ran thence N. 50° -25' E. ----- 1060.0 feet to angle -1-
" N. 47° -07' E. ----- 504.5 " " " -2-
" N. 57° -58' E. ----- 959.5 " " " -3-
" N. 49° -14' E. ----- 511.5 " " " -4-
" N. 50° -07' E. ----- 654.3 " " " -5-
" N. 33° -45' E. ----- 143.3 " " " point of Ending which is 330 feet East

of the Stone $\frac{1}{4}$ corner common to Sections 15 & 10-T. 3 N.R. 29 E.W.M. Thirty feet North Marked fence post "R" 770 for reference to terminating point.

I hereby certify that the above is a true copy of the notes taken in the above entitled Road Survey.

Feb. 27, 1915.

Willard Bradley, County Surveyor.

REPORT OF BOARD OF COUNTY ROAD VIEWERS

In the Matter of Viewing, Surveying and Laying out County Road No. 770

TO THE HONORABLE COUNTY COURT OF THE STATE OF OREGON FOR UMATILLA COUNTY.

We, the undersigned, Board of County Road Viewers, heretofore instructed to view, survey, and locate Road No. 771 submit the following report:

Pursuant to an order of the Honorable County Court, we met at the beginning point of said Road No. 770 on the 20th day of February 1915, we called to our aid H.E. McLean, Chairman, L.C. Rothrock, Chairman, W.J. Stockman, Flagman who were by the Surveyor each duly sworn. We viewed, surveyed and located said Road No. 770 as specified in our order. We find said route practicable and would respectfully recommend that said route be declared and established as a public highway, of Umatilla County, Oregon.

The cost of construction of said road No. 771 is estimated as follows: Grading \$75.00. The damage to property owners along the route because of the construction of said road is nothing.

Willard Bradley, County Surveyor
W.J. Stockman
L.C. Rothrock
Board of County Road Viewers of Umatilla County
State of Oregon.