

NOTES OF VACATION SURVEY OF PART OF ROAD NO. 202.

To the Honorable County Court, Umatilla County, Oregon:

I submit the following as the notes of the Survey to vacate a part of Road No. 202. Began at a point, which is a stone Mon., 1105.5 feet South of the N. W. cor. of the NE. 1/4 of Sec. 30 T. 4N.; R 32 EWM. Ran thence South 7°-27' E. 189.5 ft. thence S. 59°-56' E. 527.0 ft, and there terminating.

A strip 30 ft. wide on each side of the above described center line to be vacated, where not included in Road No. 772, as located.

I hereby certify that the above is a true copy of the notes taken in the above entitled Road Survey made May 19th, 1915.

Willard Bradley, County Surveyor.

REPORT OF BOARD OF COUNTY ROAD VIEWERS.

In the Matter of Viewing, Surveying and Laying out County Road No. 773.

To The Honorable County Court of the State of Oregon, for Umatilla County.

We, the undersigned, Board of County Road Viewers, heretofore instructed to view, survey, and locate Road No. 773, submit the following report:

Pursuant to an order of the Honorable County Court, we met at point of beginning of Road No. 773, on the 20 day of May, 1915, We called to our aid

H. E. McLean, Chairman
L. C. Rothrock, Chainman
W. J. Stockman, Flagman.

who were by the Surveyor each duly sworn. We viewed, surveyed, and located said Road No. 773, as specified in our order. We find said route practical and that the damages caused by creating said road will be nothing, as the roadway has been traveled for years. Estimated cost of construction - 1-30 ft. bridge - - \$900.

We respectfully recommend that the above road be adopted.

Willard Bradley, Board of County Road Viewers of Umatilla County, State of Oregon.
W. J. Stockman
L. C. Rothrock

NOTES OF SURVEY OF ROAD NO. 773.

Surveyed May 20-1915.

To the Honorable County Court, Umatilla County, Oregon.

I submit the following as the notes of the Survey of Road No. 773.

Began at a point in the center of Road No. 535 which point is approximately the S. W. cor. of the S. E. 1/4 of S. W. 1/4 Sec. 36 T. 6N.; R. 34 E. W. M. Set post 4"x4"x4' 20 ft. west, dug pits and raised mound around stake. Ran Thence,

N. 89°-0' E. --- 1044.0 ft. from point of beginning.
thence N. 87°-55' E. --- 3936.0 ft. " " " to a stone mon. at cor. of townships, 6N. 34 E. W. M.
5N. 34 "
6N. 35 "
5N. 35 "
thence East - - - - - 5069.0 ft. from point of beginning.
" N. 88°-30' E. -- 5280.0 " " " set mile post -I- a stake 4"x4"x4' 20 ft. north dug pits and raised mound.
" N. 88°-30' E. -- 6576.0 ft. from point of beginning.
" N. 87°-53' E. -- 9254.0 " " " to a stone mon. the S. E. cor. Sec. 31 T. 6N.; R 35 E. W. M.
" N. 88°-15' E. -- 9784.0 ft. from point of beginning.
" N. 88°- 0' E. --10560.0 " " " set mile post -2- 20 ft. north, a stake 4"x4"x4'. dug pits and raised mound.
" N. 88°- 0' E. --11770.0 ft. from point of beginning, center of Dry Creek -30- ft. wide.
" " --11900.0 ft. from point of beginning to stone 1/4 cor. common to Secs 32 T. 6 N.: R. 35 E. W. M. and Sec. 5 T. 5 N.; R 35 EWM
Thence N. 72°-03' E. --12414.0 ft. from point of beginning.
" S. 72°-07' E. --12886.0 " " "
" N. 88°- 0' E. --13467.0 " " "
" N. 88°-14' E. --14605.0 " " " to stone cor. S. E. cor. Sec. 32 T. 6 N.: R 35 E. W. m.
" N. 88°-14' E. --14896.0 ft. from point of beginning a point 30 ft. west of Barrett warehouse.
" N. 31°-18' E. --15421.0 ft. from point of beginning.
" N. 28°-14' E. --15840.0 " " " set mile post -3- a 4"x4"x4' 20 ft. left. Dug pits and raised mound.
" N. 28°-14' E. --16147.0 ft. from point of beginning.
" N. 61°- 0' E. --16585.0 " " "
" N. 2°-13' W. --16655.0 " " " to a point 10 ft. East of 1/16 cor stone.
" N. 2°-13' E. --17984.0 from point of beginning to a point of ending being the 1/16 cor stone at NE. cor. of NE. 1/4 of SW. 1/4 Sec. 33 T. 6 N.: R. 35 E. W. M.

I hereby certify that the above is a true copy of the notes taken in the above entitled Road survey.

Willard Bradley, County Surveyor.

May 26, 1915.