



2003-4420363 1 of 2

IN THE BOARD OF COUNTY COMMISSIONERS OF UMATILLA COUNTY

STATE OF OREGON

442 0363

RECEIVED

**IN THE MATTER OF LEGALIZATION)
OF A PORTION OF FRUITVALE ROAD,))
COUNTY ROAD NO. 508)**

JUL 16 2003
UMATILLA COUNTY
RECORDS

ORDER NO. RD2003-22

WHEREAS, the Umatilla County Board of Commissioners may, under authority of ORS 368.201 to 368.221, order a county road that has been used and traveled by the public for ten (10) years or more to be surveyed and recorded, and

WHEREAS, the Umatilla County Board of Commissioners ordered the survey of Fruitvale Road (County Road #508), the midpoint of which is located approximately 1 mile northeast of Umapine in Umatilla County, Oregon, and lies in Sections 18 and 19, Township 6 North, Range 35 E.W.M, and

WHEREAS, the Notice of Hearing was posted and all owners of abutting property affected by the legalization procedure were served copies of the Notice of Hearing, and

WHEREAS, the Umatilla County Board of Commissioners on July 16, 2003, held a public hearing and finding that it would be in the public interest to legalize the road:

THEREFORE IT IS NOW ORDERED that the road be legalized as follows:

A 40-foot wide strip of land for road purposes located in Sections 18 and 19, Township 6 North, Range 35 East of the Willamette Meridian, the centerline of which is more particularly described as follows:

Commencing at a brass disk in the center of Oregon State Highway No. 332 which marks the Southwest Corner of Section 18, Township 6 North, Range 35 E.W.M.; thence N00°00'48"W, 446.10 feet on a line between said Southwest Corner of Section 18 and a brass disk marking the closing corner to Section 13, Township 6 North, Range 34 E.W.M. and Section 18, Township 6 North, Range 35 E.W.M. on the Oregon-Washington State Line to Engineer's Station 0+00.00 and the true point of beginning of this description; thence S77°19'06"E, 1220.38 feet; thence 166.56 feet along a 452.77-foot radius curve right (the long chord bears S66°46'45"E, 165.63 feet); thence S56°14'25"E, 63.67 feet; thence 155.99 feet along a 260.86-foot radius curve left (the long chord bears S73°22'16"E, 153.67 feet); thence N89°29'53"E, 1131.27 feet; thence N89°31'04"E, 1326.51 feet; thence S89°51'27"E, 1320.01 feet to a brass-capped monument marking the Southeast Corner of Section 18, Township 6 North, Range 35 E.W.M. and the terminus of this description. EXCEPTING THEREFROM that portion of the above described road lying within the right-of-way of Oregon State Highway No. 332.

The plat of the above described road is recorded as Survey No. 03-81-C in the Umatilla County Surveyor's Office

Dated this 16th day of July, 2003

Original to: Commissioner's Journal
Copy to: Doug Olsen, County Counsel

UMATILLA COUNTY BOARD OF COMMISSIONERS

ABSENT

William S. Hansell, Chairman

Emile M. Holeman
Emile M. Holeman, Commissioner

Dennis D. Doherty
Dennis D. Doherty, Commissioner



ATTEST: OFFICE OF COUNTY RECORDS

By: *Jean Hemphill*
Records Officer

APPROVED AS TO FORM:

Doug Olsen
Doug Olsen, County Counsel



State of Oregon)
County of Umatilla)

This instrument was received
and recorded on
07-18-03 at 3:15

in the record of instrument
code type DE-ORDER

Instrument Number 2003-4420363
Fee 0.00

Office of County Records

Jean Hemphill
Records Officer