

Field Notes, Road 325 for Umatilla County, Oregon.

I meet Jno. Hughes and Peter Gerking, Monday Apr. 22nd 1889, and administer the usual oath. We select J. S. Hodgen and U. A. Ward to chain and Wm. Chastain to mark, who qualify as directed by law.

I commence at point, purporting to be $\frac{1}{16}$ S. cor. bet. Secs 21 + 22 T. 6 N. R. 35 E. - Set initial post 30 links South of point and run, thence, on var. 20° (very rainy)

East 11.00 chs Set angle post at point and turn, left, $75^\circ = 75$ az. course

N. $15^\circ 00' E$ 22.50 " Through cut in the Baker R. R. 33 ft deep. Set angle post at pt. and turn

N $10^\circ 30' W$ 31.40 " Int. true line bet. Secs. 15 + 22 at 11.83 chs dist. East of Sec. cor. I set angle post at pt. and cut A on South side of post in fence, course E + W. 38 links N. of pt. I turn thence Right on line bet. Secs. 15 + 22.

East 59.26 " Little Walla River 28 links, Gen. Course North

59.56 " $\frac{1}{4}$ S. cor. which parties claim to have been set by J. H. Raley, when Co. Surveyor.

80.00 " Set 1 mile post 30 links North of pt.

16.64 " Cor. for Secs. 14, 15, 22 + 23 T. 6 N. R. 35 E. I set angle post at point, and turn on line bet Secs. 22 + 23

South 36.65 " To $\frac{1}{16}$ S. cor. on N. $\frac{1}{2}$ of line bet. said Secs 22 + 23. I set angle post at pt. and turn on line through center of N. $\frac{1}{2}$ of Sec 23. Ascend

East 45.00 " Summit.

47.00 " Descend.

53.10 " Spring branch, 10 lks wide, runs N.

56.72 " Center Cor. for N.W. $\frac{1}{4}$ Sec. 23.

71.09 " Little Walla River 15 lks. wide, runs N.W.

73.03 " Spring branch 6 " " " " " " " " " " " "

77.00 " $\frac{1}{16}$ S. cor. on N. $\frac{1}{2}$ of line N. + S. through center Sec 23. I set terminus. 45 links East against fence on E side of lane N. + S.

Monday Apr. 22nd 1889
 I hereby certify that the foregoing notes of road survey no. 325 for Umatilla County, Or. are correct.

Jno. C. Arnold
 County Surveyor.