

UMATILLA COUNTY, OREGON

FIELD NOTES

COUNTY Road No. 872

Date September 1927

STATION	Curve Data	Length of Tangents and Curves	Bearing	REMARKS
0/00		162.8	N. 76°55'E	Beginning of project, equals Sta/ 329/65 of the Eagle Creek Market Road.
1/62.8 P.I.	1°49' R.	1799.1	N.87°44'E.	
19/61.9 P.C.	10° C.R.	316.3		
22/78.2 P.T.	31°38'	310.8	S.60°38' E.	
25/89.0 P.C.	56° C.L.	192.1		
27/81.1 P.T.	107°34'	24.9	N.11°48'E.	
28/06.0 P.C.		273.0		
30/79.0 P.T.		1147.5	N.88°14' E.	The Quarter corner common to sections 15 and 22 is 151.1 feet west of Sta. 30/79.0 P.T.
42/26.5 P.I.	0°28' L.	2623.1	N.87°46'E.	
68/49.6 P.I.	0°22' L.	1296.6	N.87°24'E.	
81/46.2 P.I.	0°19'R.	2545.66	N.87°43'E.	Which is coincident with the quarter section corner common to sections 14 and 22.
106/91.8 P.C.	56° C.L.	159.6		The P.I. of the curve is coincident with the southeast corner of section 14.
108/51.4 P.T.	89°23'	1121.3	N.1°40' W.	
119/72.7 P.C.	20° C.R.	393.5		
123/66.2 P.T.	78°42'	1688.1	N.77°02'E.	
140/54.3 P.C.	4° C.R.	345.0		
143/99.3 P.T.	13°48'	3279.3	S.89°10'E.	
176/78.6 P.O.T.		70.4		Which is a point on the Range line between Range 35 and 36.
177/49.0 P.C.	2° C.R.	301.7		
180/50.7 P.T.	6°02'	835.3	S.83°08'E.	
188/86.0 P.C.	4° C.R.	227.5		
191/13.5 P.T.	9° 06'	342.1	S.74°02'E.	
194/55.6 P.C.	4° C.L.	329.6		
197/85.2 P.T.	13°11'	451.1	S.87°13'E.	Which point is 152.5 feet North of the Southeast corner of the Northeast quarter of the Southwest quarter of section 18, T. 3 N., R. 36 E. W.M. and is the end of said County Road No. 872
202/36.3 P.O.T. ✓				