

-----NOTES OF THE SURVEY OF ROAD NO.778. -----

Survey made , March 13, -14-15, and 16th. 1916.

Party.

L.C.Rothrock, chainman.

Henry Mills, "

W.J.Stockman, Flagman.

Willard Bradley, County Surveyor, Transitman.

Began at a point 200 feet North of the center of Section 20, T.3.N.:
R.33 E.W.M., at which point we placed a stone 10"x10"x14" marked Rx, 14"
in the ground, from which a fence post marked R.778 Bears N.85°W. 19.6
feet.

" " " " " " " " S.71°40'E.

23.3 feet.

Thence to the Southwest by a curve of 200 feet radius, 314.1 feet, to
a point on the East and West center line of Section 20.

Thence , N.89°-20'W. 913.0 feet.

" , by a curve to the left of 200 feet radius 125.6 feet.

" , S.31°-10'W. ----373.6 feet.

" S.21°-37'W. -----543.7 " .

" S.41°-32'W. ----- 530.0 " .

" S.14°-17'W. ---- 400.0 " .

" S.2°-28'E. --- 500.0 " .

" S.7°-05'W. ---- 300.0 " .

" S.10°-55'E. ---- 219.8 " to a point on the section line between
Sec's.20&29- 2051.5 feet West of the
¼ corner.

----- 400.0 "

" S.7°-07'E. ---- 500.0 " .

" S.15°-14'E. -- 150.0 " .

" S. 0°-10'E. --- 150.0 " .

" S. 7°-30'E. --- 80.0 " Mile post (1) one , turned right
angle to line to left and at 25 ft.
set stone marked MI , and at 37.3
ft, marked cross on bluff, at 4 ft.

--- 310.0 " ←
---- 345.0 " . height.
-I- Ravine.

Thence , S.51°-50'E. -----283.0 feet.
 " S.63°-20'E. ----- 272.0 " .
 " S.78°-45'E. ----- 420.0 " .
 " S.45°-26'E. ----- 169.0 " ..
 " S.13°-0'E. ----- 611.0 " .
 " S.37°-09'E. ----- 347.0 " to a point on the center line
 of section 29-,530.1 feet west
 of the center of the section.

-----400.0 "
 2 S.21°-0'E. ----- 400.0 "
 " S.24°-17'E, ----- 300.0 "
 " S.56°-35'E. ----- 70.0 " *To Ravine.*
 ----- 500.0 "
 " S.23°-46'E. -----265.0 "
 " S.12°-14'W. ----- 180.0 "
 " S.26°-07'W. ----- 400.0 " to point of terminating ,

which is a spike in the center of the macadam road. From which a
 power pole marked R.778 bears S.87°-05'E. 70.7 feet.

And S.87°-05'W. 60.0 feet a set stone marked R.x .
 " " " " 25.3 " a stone in a stone wall marked x,.

The point of terminating is N.5°-45'E. ^{900'} of $\frac{1}{4}$ cor. common to Secs.
 29 & 32 , T.3 N.; R33 E.W.M.

I hereby certify that the above is a true copy of the notes
 of the survey of Road No.778.

Willard Bradley

 County Surveyor.