

FILED  
J. DEAN FOUQUETTE, SR.  
UMATILLA COUNTY CLERK

1987 JUL -1 P 1:51

Board of County Commissioners  
Umatilla County, Oregon

In the matter of Legalization of)  
Tutuilla Road (County Road 915) )

Order No. \_\_\_\_\_


Whereas, Tutuilla Road (County Road 915) from Oregon State Highway Engineers Station 6 + 83.18 P.T. as shown on Oregon State Highway Map Drawing No. 10C-45-24 (August, 1986) to the Southerly boundary of Grecian Heights P.U.D. to the City of Pendleton, Oregon has been surveyed, notice of public hearing has been served and posted, and a public hearing has been held pursuant to ORS 368.201 to 368.211; and

Whereas, there are no unresolved claims made under those proceeding;

NOW, THEREFORE, The Umatilla County Board of County Commissioners Orders:

1. Within sixty days of today, the City of Pendleton shall survey the road in compliance with ORS 368.106; and
2. That Tutuilla Road (County Road 915) from Oregon State Highway Engineers Station 6 + 83.18 P.T. as shown on Oregon State Highway Map Drawing No. 10C-45-24 (August, 1986) to the Southerly boundary of Grecian Heights P.U.D. to the City of Pendleton, Oregon be legalized as described on attachment "A" hereto.

July 1, 1987



Attest  
J. Dean Fouquette, Sr  
County Clerk

Umatilla County Board of County Commissioners, by

*Glen Young*  
Chairman

*William S. Hansell*  
Commissioner

*ABSENT*  
Commissioner

RECEIVED

MAR 10 2005

UMATILLA COUNTY RECORDS

Order No \_\_\_\_\_

Original to: Commissioner's Journal



2005-4780370 2 of 3

*HL 10/11*

COUNTY ROAD 915  
(TUTULLIA ROAD)  
RIGHT-OF-WAY DEDICATION

May 8, 1987

A 60.00 foot road right-of-way lying in the S. W. 1/4 of Section 10 and in Section 15 T2N R32 E.W.M., the centerline of which is more particularly described as follows:

Commencing at the Southwest corner of Section 10 T2N R32 E.W.M.

Thence North 69° 09' 29" East a distance of 547.92 feet to a point being Oregon State Highway Engineers Station 6 + 83.18 P. T. as shown on I-84 Highway Map Drawing No. 10C-45-24 dated August 1966 said point being the true point of beginning for this description;

Thence along a circular curve to the left a distance of 140.29 feet, said curve having a central angle of 58° 13' 15" a radius of 138.06 feet and a L. C. of (South 53° 56' 33" East a distance of 134.33 feet);

Thence South 83° 03' 10" East a distance of 343.56 feet;

Thence along a circular curve to the right a distance of 188.40 feet. Said curve having a central angle of 23° 33' 00" a radius of 458.37 feet and a L. C. of (South 71° 16' 40" East a distance of 187.08 feet);

Thence South 59° 30' 10" East a distance of 165.77 feet;

Thence along a circular curve to the left a distance of 199.93 feet, said curve having a central angle of 37° 59' 00" a radius of 301.58 feet and a L. C. of (South 78° 29' 40" East a distance of 196.29 feet);

Thence North 82° 30' 50" East a distance of 289.58 feet;

Thence along a circular curve to the right a distance of 277.78 feet, said curve having a central angle of 33° 20' 00" a radius of 477.47 feet and a L. C. of (South 80° 49' 10" East a distance of 273.88 feet);

Thence South 64° 09' 10" East a distance of 151.40 feet;

Thence along a circular curve to the right a distance of 707.93 feet said curve having a central angle of 55° 08' 00" a radius of 735.70 feet and a L. C. of (South 36° 35' 10" East a distance of 680.94 feet);

Thence South 9° 01' 10" East a distance of 501.36 feet;

Thence along a circular curve to the left a distance of 639.08 feet said curve having a central angle of 48° 23' 49" a radius of 756.59 feet and a L. C. of (South 33° 13' 04" East a distance of 620.25 feet);

Thence South 57° 24' 59" East a distance of 76.36 feet;

Thence along a circular curve to the right a distance of 188.64 feet, said curve having a central angle of 6° 36' 00" a radius of 1637.66 feet and a L. C. of (South 54° 06' 59" East a distance of 188.54 feet);



A10 1081

Thence South 50° 48' 59" East a distance of 178.47 feet;

Thence along a circular curve to the right a distance of 415.35 feet said curve having a central angle of 20° 06' 00" a radius of 1183.96 feet and a L. C. of (South 40° 45' 59" East a distance of 413.22 feet);

Thence South 30° 42' 59" East a distance of 1000.99 feet;

Thence along a circular curve to the right a distance of 191.91 feet said curve having a central angle of 7° 51' 11" a radius of 1400.14 feet and a L. C. of (South 26° 42' 23" East a distance of 191.76 feet);

Thence South 22° 51' 48" East a distance of 101.40 feet;

Thence along a circular curve to the right a distance of 520.83 feet said curve having a central angle of 1° 44' 10" a radius of 17,188.75 feet and a L. C. of (South 21° 59' 43" East a distance of 520.81 feet);

Thence South 21° 07' 38" East a distance of 349.18 feet;

Thence along a circular curve to the right a distance of 216.54 feet said curve having a central angle of 9° 03' 52" a radius of 1368.75 feet and a L. C. of (South 16° 35' 42" East a distance of 216.32 feet);

Thence along a circular curve to the right a distance of 292.18 feet said curve having a central angle of 4° 41' 56" a radius of 3562.70 feet and a L. C. of (South 9° 42' 48" East a distance of 292.10 feet) more-or-less to an intersection with the Easterly extension of the Southerly boundary of Grecian Heights P.U.D. to the City of Pendleton, said intersection being the terminus point of this description.

All being in the County of Umatilla, State of Oregon, further depicted in Exhibit "A" attached hereto and made a part hereof.

State of Oregon )  
County of Umatilla )

This instrument was received and recorded on 03-10-05 at 2:00

In the record of instrument code type DE-ORDER

Instrument Number 2005-4780370  
Fee 0.00

Office of County Records

Records Officer