

UMATILLA COUNTY ROAD DEPARTMENT

ROADWAY DESCRIPTION FOR RELOCATION OF WALCHI BRIDGE

A strip of land located in the Southwest quarter of the Northwest quarter and in the Southeast quarter of the Northwest quarter of Section 8, Township 4 North, Range 29 East, Willamette Meridian, Umatilla County, Oregon, said strip of land being 60.00 feet wide, lying 30.00 feet on each side of the following described centerline:

Commencing at a 7/8-inch diameter iron rod found at the Northeast corner of said Section 8, thence S 00°51'59" W 3,993.10 feet to a 5/8-inch diameter iron rod found 30 feet westerly from the South 1/16 corner between said Section 8 and Section 9, T4N, R29E, thence N 62°45'17" W 4,669.00 feet to a point on the existing centerline of Umatilla County Road No. 1200 (Loop Road) and the TRUE POINT OF BEGINNING of this centerline description;

THENCE along said centerline of said 60.00-foot wide strip of land the following courses and distances:

417.92 feet along the arc of a 2,864.79 foot radius circular curve, concave southeasterly (the long chord of which bears N 76°51'00" E 417.55 feet) to a point,

N 81°01'46" E 570.76 feet to a point, and

417.92 feet along the arc of a 2,864.79 foot radius circular curve, concave southerly (the long chord of which bears N 85°12'30" E 417.55 feet) to a point on the existing centerline of said Umatilla County Road No. 1200 and the point of termination of this description of said 60.00-foot wide strip of land.


NOTE:

From the TRUE POINT OF BEGINNING of this description:

- The 7/8-inch diameter iron rod described herein and depicted on Umatilla County Survey No. 86-66-A bears N 66°13'33" E 4,601.87 feet,
- A 1/2-inch diameter iron rod found at the Southwest corner of Parcel A, as said Parcel A is depicted on Umatilla County Survey No. 84-17-Ax, bears S 73°10'28" W 3,476.21 feet,

- A 1/2-inch diameter iron rod found along the northerly right-of-way line of Umatilla County Road No. 1200, opposite the northwesterly corner of the 1.98 acre parcel of land surveyed and depicted on Umatilla County Survey 89-22-A, bears S 73°05'56" W 4,051.65 feet.

The basis of the bearings given in this description is Umatilla County Survey No. 86-66-A.



April 16, 1990

Prepared by:

Gary L. Langlitz
Gary L. Langlitz,
Oregon Land Surveyor No. 1099
Anderson-Perry & Associates, Inc.