

AMENDED FIELD NOTES OF COUNTY ROAD NO. 712.

I commence at the $\frac{1}{4}$ sec. corner on the N. side of sec, 5 T. 4 N., R. 28 E. W. M. At a point 20 ft. S. & 20 ft. W. of aforesaid point I set a post, 4 ft. long, 4 ins. square, marked R. 712; dug pits, 18 X 18 X 12 ins. N. & S. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. Thence following the subdivisional section line south 80.00 chs. to a point from which I set, to the right, 20 ft. distant, a post, 4 ft. long, 4 ins. square, marked 1 M; dug pits, 18 X 18 X 12 ins., N. & S. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence south 1.10 chs. to the $\frac{1}{4}$ sec. corner between secs. 5 & 8 angle 1. Thence west 78.90 chs. to a point from which I set to the right, 20 ft. distant, a post 4 ft. long, 4 ins. square, marked 2 M; dug pits, 18 X 18 X 12 ins., N. & S. of post, and raised mound of earth, 18 ins. high, 4 ft. base around post. Thence west. 7.60 chs. to irrigation canal 25 lks. wide, course north. Thence west 30.34 chs. to the N. W. corner of sec. 7 in said township and range, angle 2. Thence south 22.40 chs. to irrigation canal 25 lks. wide, course N. E. Thence south 19.76 chs. to a point from which I set to the right, 20 ft. distant, a post, 4 ft. long, 4 ins. square, marked 3 M; dug pits, 18 X 18 X 12 ins., N. & S. of post, raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence south 39.88 chs. to the S. W. corner of sec. 7 in said township and range from which I set, 20 ft. N. & 20 ft. E. a post, 4 ft. long, 4 ins. square, marked R. T. 712; dug pits E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

I hereby certify that the foregoing field notes of County road No. 712 are correct according to survey thereof, commenced on the 23'd day of May 1911.

Gary Kimbrell
Surveyor for Umatilla County, Oregon.