

FIELD NOTES OF COUNTY ROAD NO. 713.

I commence at the west end of the County steel bridge on the section line between Secs. 8 & 17 T. 4 N., R. 28 E., W. M. At a point 30 ft. W. and 20 ft. S. of aforesaid point, I set a post, 4 ft. long, 4 ins square, marked R. 713: dug pits, 18 x 18 x 12 ins., S. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence West 30 lks. to angle 1

,, S. 6° 32' E. 13.32 chs. to angle 2

,, S. 20° 25' E. 7.37 ,, ,, ,, 3

,, S. 27° 7' E. 5.32 ,, ,, the line between Secs.

16 & 17 in said township and range. angle 4. Thence following the said section line South 41.53 chs. to angle 5. Thence N. 75° 45' W. 11.15 chs. to angle 6. Thence N. 71° 26' W. 1.01 chs. to a point from which I set, to the left 20 ft. distant, a post, 4 ft. long, 4 ins. square, marked 1 M: dug pits, 18 x 18 x 12 ins., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence N.

71° 26' W. 7.46 chs. to angle 7

,, N. 80° 43' W. 4.32 chs. ,, ,, 8

,, S. 75° 28' W. 6.88 ,, ,, ,, 9

,, N. 79° 44' W. 4.07 ,, ,, ,, 10

,, S. 73° 8' W. 17.53 ,, ,, ,, 11

,, S. 8° 17' W. 13.40 ,, ,, the line between Secs.

17 & 20 from which I set, 20 ft. S. a post, 4 ft. long, 4 ins. square, marked R. T. 713: dug pits E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

I hereby certify that the foregoing field notes
of County road No. 713 are correct according to survey
made by me: commenced on the 23'd day of May 1911.

Gary Kimbrell

Surveyor for Umatilla County, Oregon.