

FIELD NOTES OF ROAD NO 698.

I commence at the southwest corner of the N. W. 1/4 of section 32 T. 5 N., R. 29 E., W. M. At a point 20 ft. S. and 30 ft. E. of said corner I set a post, 4 ft. long, 4 ins. square, marked R. No. 698; dug pits, 18 X 18 X 12 ins., E. and S. of post, and raised a mound of earth, 18 ins. high, 4 ft. base, around post.

Thence, following the subdivisional section line, I run east 19.08 Chs. to irrigation ditch 4 ft. wide, course N. E.

23.78 Chs. to irrigation ditch 12 ft. wide, course N. E.

32.58 Chs. to gully 7 ft. wide, course N.E.

59.28 Chs. to irrigation ditch 3 ft. wide, course N.

79.17 Chs. to bank 8 ft. high, course N. & S.

76.25 Chs. to seepage ditch from Government Reservoir,
/course N.

80.54 Chs. the southeast corner of the N. E. 1/4 of said section 32 in said township and range, ~~where~~
At a point 20 ft. S. of said corner
I set a post, 4 ft. long, 4 ins. square, marked R. T. No. 698; dug pits N. and S. of post, and raised a mound of earth, 18 ins. high, 4 ft. base, around post.

I hereby certify that the foregoing field notes of road No. 698 are correct as surveyed by me on the 13'th day of Feb. 1911.

Geary Kimbrell

Surveyor for Umatilla County, Oregon.