

FIELD NOTES OF HADDOX COUNTY ROAD NO. 743.

I commence at the S. W. corner of the S. E. 1/4 of Sec. 28 T. 5 N. R. 29, E. W. M., at a point 25 ft. south of aforesaid point I set a post, 4 ft. long 4 ins. square, marked R. 743: dug pits, 18 x 18 x 12 ins., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. Thence north 74.00 chs. an irrigation ditch course S. W., 79.43 chs. to the N. W. corner of the N. E. 1/4 of said section 28, a point from which I set 15 ft. W. and 20 ft. S. a post, 4 ft. long, 4 ins. square, marked R. T. 743: dug pits 18 x 18 x 12 ins. N. & S. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

I hereby certify that the foregoing field notes of Haddox County Road No. 743 are correct, according to survey made by me on the 4<sup>th</sup> day of Oct., 1912.

*Geary Kimbell*  
Surveyor for Umatilla County, Oregon.