

IN THE COUNTY COURT OF THE COUNTY OF ...

FIELD NOTES OF COUNTY ROAD NO. 716.

I commence at the 1/4 Sec. corner between Secs. 21 & 22 T. 5 N., R. 29 E., W. M. At a point 30 ft. W. and 20 ft. S. of beginning, I set a post, 4 ft. long, 4 ins. square, marked R. 716; dug pits, 18 x 18 x 12 ins., S. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. Thence following the subdivisional section line west 80.00 chs. to a point from which I set, to the S. 20 ft. distant, a post, 4 ft. long, 4 ins. square, marked 1 M; dug pits, 18 x 18 x 12 ins., E. & W. of post and raised mound of earth, 18 ins. 4 ft. base, around post. 80.54 chs. 1/4 Sec. corner between Secs. 20 & 21 in said township and range; 160.00 chs. to a point from which I set, to the S. 20 ft. distant, a post, 4 ft. long, 4 ins. square, marked 2 M; dug pits, 18 x 18 x 12 ins., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. 160.62 chs. 1/4 Sec. corner between Secs. 19 & 20 in said township and range; 240.00 chs. to a point from which I set, to the N. 20' ft. distant, a post, 4 ft. long, 4 ins. square, marked 3 M; dug pits, 18 x 18 x 12 ins., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. 241.18 chs. 1/4 Sec. corner on the west side of Sec. 19 in said township and range. 274.00 chs. concrete pipe line. 296.00 ,, irrigation ditch 8 lks. wide. 320.00 ,, to a point from which I set, to the N. 20 ft. distant, a post, 4 ft. long, 4 ins. square, marked 4 M; dug pits, 18 x 18 x 12 ins., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

IN THE COUNTY CORNER OF THE SEVERAL OF OREGON FOR AMPLIFY CORNER

321.26 chs. 1/4 Sec. corner between Sec's 23 & 24 T. 5 N.,
R. 28 E., W. M. 400.00 chs. to a point from which I set, to
to the S. 20' ft. distant, a post, 4 ft. long, 4 ins.
square, marked 5 M: dug pits, 18 x 18 x 12 ins., E. & W.
of post, and raised mound of earth, 18 ins. high, 4 ft.
base, around post. 480.00 chs. to a point from which I
set, to the S. 20' ft. distant, a post, 4 ft. long, 4 ins.
square, marked 6 M: dug pits, 18 x 18 x 12 ins., E. & W.
of post, and raised mound of earth, 18 ins. high, 4 ft. base,
around post. 498.00 chs. to angle 1
Thence N. 43° 43' W. 11.56 chs. to angle 2
,, S. 81° 58' W. 2.19 ,, ,, ,, 3
,, S. 37° 50' W. 10.24 ,, ,, the east and west center
line of section 21 in said township and range.
Thence following said center line of section 21 west 18.00
chs. to the east line of the right of way of the Huntington
line of the O. W. R. and N. Co's railroad, where I set,
a post, 4 ft. long, 4 ins. square, marked R. T. 716: dug
pits N. & S. of post, and raised mound of earth, 18 ins.
high, 4 ft. base, around post.

I hereby certify that the foregoing field notes
of County road No. 716 are correct as surveyed by me on
the 26th day of May, 1911.

Geary Kimball
Surveyor for Umatilla County, Oregon.