

E 1/4 14
E 1/4 13
W 1/4 13

FIELD NOTES OF COUNTY ROAD NO. 715.

I commence at the 1/4 Sec. corner between Secs. 13 & 14 T. 5 N., R. 28 E., W. M.. At a point 30 ft. south from aforesaid point I set a post, 4 ft. long, 4 ins. square, marked R. 715; dug pits, 18 & 18x12., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. Thence following the subdivisional section line west 80.00 chs. to a point from which I set, to the left, 30 ft. distant, a post, 4 ft. long, 4 ins. square, marked 1 M; dug pits, 18 x 18 x 12 ins., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. Thence following the subdivisional Sec. line west 160.00 chs. (80.00 chs. (?)) to a point from which I set, to the left, 30 ft. distant, a post, 4 ft. long, 4 ins. square, marked 2 M; dug pits, 18 x 18 x 12 ins., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. Thence following the subdivisional section line west 40.40 chs. to the center of Sec. 16 in said township and range. Thence following the subdivisional Sec. line west 17.42 chs. to angle 1.

W 1/4 13 }
W 1/4 14 }
W 1/4 15 }
W 1/4 16 }
40 e17

Thence North 2.27 chs. to angle 2.

,, S. 80° 40' W. 14.00 ,, ,, ,, 3.

,, S. 73° W. 5.91 ,, ,, a point from

which I set, to the left, 30 ft. distant, a post, 4 ft. long, 4 ins. square, marked 3 M; dug pits, 18 x 18 x 12 ins., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence S. 73° W. 2.09 chs. to angle 4.

,, N. 82° 22' W. 0.60 ,, irrigation ditch 20 lks. wide

Notary Public

6.55 chs. O. R. and N. Co's railway track

8.30 ,, to the old Umatilla and Echo road from which I
set 33 ft. S. a post, 4 ft. long, 4 ins. square, marked
R. T. 715: dug pits E. & S. of post, and raised mound of
earth, 18 ins. high, 4 ft. base, around post.

I hereby certify that the foregoing field
notes of County road No. 715 are correct as surveyed by
me on the 27th day of May, 1911.

Geary Kimbrell

Surveyor for Umatilla County, Oregon.

Notary Public