

---Notes of Survey of Road No. 77I.-----

Feb. 17 to 20 1915.

To the Honorable County Court.)  
Umatilla County Oregon. )

I submit the following as  
the notes of the survey of Road No. 77I . Began at a  
granite stone which marks the south west corner of Sec.  
31, T.3N.; R.28 E.W.M., which is a point in the center of  
Road No. 173. Set 4"x4" reference stake 20 feet East  
marked "R" 77I.

ran thence ,N.56°-19'E. ----- 5280 feet , set mile post

-1- a 4"x4" stake

20 feet to the right.

" " ----- 9,571 Feet  $\frac{1}{4}$  Sec cor. post

between Sects. 29 &

32 bears N.63°-18'W.

4.5 feet.

" " ----- 10,560 feet, set stone on center

Line and 4"x4" stake 20

feet to the right for

mile point -2-.

" " ----- 12,560 Feet , ravine 3 ft. deep

and 20 ft. wide.

" " ----- 12,997 feet, N.14°-41'E. to

post  $\frac{1}{4}$  cor. Sections

28 & 29 .

" " ----- 13,877 feet .N.74°-26'W. to post

$\frac{1}{4}$  cor .Sections 28 & 29.

" " ----- 15,840 feet , set mile post -3-

a 4"x4" stake 20 ft. to

the right.

" " ----- 19,123.5 feet , Section cor. post

of Cors. 21-22-27-28-  
bears S.42°-15'E. 49.3  
feet.

N.56°-19'E. -----21,120 feet .set stone on center  
line and set 4"x4" post 20  
feet to the right to mark  
mile -4-.

" " ----- 22,120 feet, foot of small Butte.

" " ----- 23,050 " cross road course E.& W.

" " ----- 25,020 " cross dry ravine 30 ft.  
wide and 4 ft. deep.  
course north.

" " ----- 26,400 feet, set 4"x4" stake 20 ft.  
to the right to mark  
mile point -5-.

" " ----- 27,050 feet, stone 1/16 cor stone bears  
N.0°-20'E. 781.0 ft.

2 " ----- 27,050 feet, Angle point -1-

Thence N.59°-81'E.----- 1,554 feet " " -2-

Which is  $\frac{1}{4}$  cor stone on  
South side of Sec. 14  
T.3 nN.:R.28 E.W.M.

Thence North -----1,317 feet, to fence running North and  
West.

" ----- 2639 feet, to a stone monument at the  
center of Section 14.

" -----2812 feet, Hinkle Ditch ,43 ft. Wide.

" -----2919 feet, to S.E. cor. of Mr. Rugg's  
barn lot.

" -----3,076 feet, set 4"x4" stake 20 feet to  
the right to mark mile point -6-.

" ----- 3,958 feet, Angle point -3- which is  
1/16 cor stone.

Thence East ---- 1317 feet, Angle point -4-.  
" North ---- Through alfalfa fields.  
" ---- 1320 feet to Stone I/I6 cor in  
present County Road No.580.  
Which is the terminating  
point called for in the order  
for the above survey. Marked fence  
post at above point "R" 771.

I hereby certify that the above is a true copy of the  
notes taken in the above entitled road survey.

Feb. 27 1915.

\* *Willard Bradley*  
-----  
County Surveyor.