

Field Notes of Road No, 746.

Commencing at a point 60 Rods East of the Center of the S,W,1/4 of Section 22,T,1,N,R,32,E,W,M,Set post 4 x 4 ins,x 4 feet long 35 feet N,E, of point,Marked R,No,746 made mound 4' Base 18''high around post.

Thence N,1°W 34.50 Chs,.....A,1
..1° Curve left 12,00 Chs,.....46,50 ,,,,,, ,,,,,,A,2,
..N,9°40'W,.....33,50.....80,00 set post 4 x 4 inches x 4 feet long 20feet to right Marked 1,M, made mound 4 ft,Base 18 ins, high around post, Thence N,9°40'W. 31,25 chs,.... A,3,
Thence 3°30'Curve left,22,85 chs, 54,10.. A.4
,, N,46°50'W! ...25,90 ... 80,00 Set post 4 x 4 ins,x 4 feet long Marked 2,M,Made mound 4 ft,Base,18,ins,high around post, thence N,46°50'W, ,50 spring branch 2,00A,5
thence 3°30'Curve Right 11,25 chs,.....15,25,.....A,6
.. N,3°30'W,46,00 chs,.....59,25.....A.7
thence 3°Curve left 13,15,chs,.....72,40.....A.8
.. N,25°30'W, 7,60,,,,,.....80,00 Set post 4 x4 ins, x 4 feet long 20 feet to left marked 1,M, made mound 4'Base. abd 18 ins,high around,post,
Thence N,12°30'W,31,50 chs,R,T,Set post 4 x 4 ins,x 4 feet long, raised mound 4 ft,Base.18 ins,high around post 30 feet North of Terminus,Marked R,T,No,746.

I hereby certify that the foregoing Field Notes of Road No,746 are correct as Surveyed by me on the 30th,day of April 1913

John W. Kimbrell
Deputy County Surveyor.