

Field Notes of Road No,756

Commencing at the S,W,Corner of Section 18,T,1,N,R,32,E,W,M,I set a Post 4 ins,square 3 1/2 feet long 30 feet West of the initial point, 18 ins,in the ground Marked R,No,756 dug pits 18 ins,square 12 ins, deep E,&W,of post 5 feet distant,and raised mound of earth 18 ins, high around post,4 feet Base.

Thence 1 run between Sections,18 & 19 East 80,00 l.M.Set post 4 ins, Square 3 1/2 feet long 20 feet to the right marked l,M, dug pits,18 ins,square 12 ins,deep E,&W,5 feet distant,and raised mound of earth 4 feet Base,18 ins,high around post.

Thence East 46,96 Chains to the N,E,Corner of the N,W,1/4 of Section 20,T,1,N,R,32,E,W,M, Set post 4 ins square 3 1/2 feet long 30 feet S,W,of terminus,marked R,T,No,756 dug pits 18 ins square 12 ins,deep S,&W,po post 5 feet distant.and raised mound of earth 4 feet Base 18 ins,high around post.

I here by certify that the foregoing field Notes of Road No,756 are corect as surveyed by me on the 22ond,day of September 1913

J. W. Kimball.....Deputy County Surveyor.