



**NARRATIVE:**

THE PURPOSE OF THIS SURVEY WAS TO SET THE CORNERS OF MY CLIENT'S PROPERTY WHICH CONSISTS OF LOT 3 IN BLOCK 5 OF THE ORIGINAL TOWN OF MILTON PLUS AN ADDITIONAL 3' WIDE STRIP OF LAND ADDED TO THE FRONT OF LOT 3 DUE TO THE WIDTH OF S. MAIN ST. HAVING BEEN CHANGED.

I FOUND MONUMENTS AT ALL 4 CORNERS OF BLOCK 5 AS SHOWN. I LOCATED LOT 3 BY DISTRIBUTING THE ERRORS PROPORTIONALLY AMONG ALL THE LOTS IN THE BLOCK, AND MAINTAINING THE STREET WIDTHS AS PER THE ORIGINAL PLAT.

I RAN CLOSED TRAVERSES BETWEEN THE FOUND STREET MONUMENTS AND FOR CONTROL TO SET THE LOT CORNERS, USING THEODOLITE AND E.D.M.

**LEGEND**

- MONUMENT FOUND AS NOTED
- SET 1/2" x 30" STEEL ROD WITH 1" PLASTIC CAP MKD. L.S. 934
- ( ) BRACKETS INDICATE RECORD DISTANCES

**REGISTERED PROFESSIONAL LAND SURVEYOR**

*Victor M. McLind*

**OREGON**  
JULY 17, 1970  
**VICTOR M. MCLIND**  
934

RECEIVED BY  
Umatilla County Surveyor  
Date April 1985  
Rec'd By KA  
No. 85-60-A

**SURVEY IN BLOCK 5, ORIGINAL MILTON IN NW 1/4 SE 1/4 SEC. 12, T5N, R35E, WM.**

SURVEYED FOR VERNON RODIGHIERO

SURVEYED BY VICTOR MCLIND, L.S. 934

APRIL, 1985

SCALE: 1" = 50'

BEARINGS ARE BASED ON THE CENTERLINE OF SW. 12TH AVE AS PER THE PLAT OF COLLIER-HARRIS ADDITION.