



- denotes set 5/8" x 30" iron pin with aluminum cap stamped PLS 933
- denotes find PK nail as set by this firm, Co. Surveyor No. G-1196-A.
- denotes find PK nail, unknown origin
- denotes find R/R spike set by City of Pendleton

NARRATIVE:

This survey was performed to establish the boundaries of Lots 1, 2, 3, 12, 13 and 14, Block 105, Reservation Addition. Control was established using a R/R spike established at the intersection of SW 17th and Frazer Street during a control survey project in 1974. This control survey was used to proportion in the distance along S.W. Frazer Avenue from S.W. 17th to S.W. 11th. This same proportion was used to establish the East-West distance across Block 105. The North-South distance and the bearings were based upon the original plat of Reservation Addition.

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1" = 40'	Drn. By MLD	Drng. No. 85-07B	Revision 1
	Date 5-10-85	Ckd. By DHK	Job No. 85-62	Revision 2
Survey for CENTURY 21 Lots 1, 2, 3, 12, 13 & 14, Block 105 Reservation Addition, Pendleton		REGISTERED PROFESSIONAL LAND SURVEYOR OREGON JULY 17, 1970 DAVID H. KRUMBEIN 933		RECEIVED BY Umatilla County Surveyor Date <u>10-14-85</u> Rec'd By <u>KA</u> No. <u>85-25-A</u>

85-125-A