



- Fnd 2 1/2" Brass Caps on 1 3/4" (O.D.) I.P. Pipe at Sec. Cor. & on 1" I.P. (O.D.) @ 1/4 cor. GOULD 1940
 - 1" x 30" (I.D.) I. Pipe set with 2 3/8" Brass Cap set
 - 1/2" x 24" Rebar set with Alum. Tag # 951
- [000] of record Deed B. 142, P. 434, Thomson to UMATILLA CO.
- (000) of record 1940 GOULD Sur. - Dependent U.S. Gov.

NARRATIVE: The purpose of this survey is to stake a parcel which was recently sold by Umatilla County (Described in Deed B. 142, P. 434, Thomson to CO.) to see if a well lies on it.

I reestablished the E 1/4 Cor. of Sec. 25 from monuments of GOULD'S 1940 DEPENDENT RESURVEY OF T3N, R27E, For U.S. Dept. of Interior.

The surveyed parcel is described from said E 1/4 Cor. by bearings & distances. I assumed that the intent was that the E-W of section 25 was the cardinal direction WEST so rotated the Deed bearings to match. The East line of said parcel is coincidental with the West edge of a Driveway.

REGISTERED PROFESSIONAL LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 18, 1971
G. DENNIS EDWARDS
951

SURVEY FOR KENT MADISON
IN SEC. 25, T3N, R27E, W.M.
UMATILLA COUNTY, OREGON
4/18/90 Rev. 7/11/90 Job # 5900+023
EDWARDS SURVEYING P.O. BOX 763
567-3336 HERMISTON, OREGON

90-52-A
7-90
KA
90-52-A