



NARRATIVE OF SURVEY

LOCATION: S.E.  $\frac{1}{4}$  of Sec. 25, T. 2 N., R. 34 E., W.M.

SURVEYED FOR: Faith Media

Purpose of Survey: To Locate corners of W  $\frac{1}{2}$  of SW  $\frac{1}{4}$  of SE  $\frac{1}{4}$  of Sec. 25

MONUMENTS FOUND (used for control):  $\frac{1}{4}$  cor bet. Sections 25 and 36, E.  $\frac{1}{16}$  corner bet. Sections 25 and 36, C-S  $\frac{1}{16}$  corner of Sec. 25, SE  $\frac{1}{16}$  corner of Sec. 25, all 2" pipes with Brass Caps stamped "Indian Allotment"

OTHER MONUMENTS FOUND (not used for control): Sec. Cor 25, 30, 31, 36; S  $\frac{1}{16}$  corner bet. Sections 25 and 30;  $\frac{1}{4}$  cor. bet Sections 25 and 30; and Center  $\frac{1}{4}$  corner of Sec. 25; all 2" iron pipes with Brass Caps stamped "Indian Allotment"

MONUMENTS SET:  $\frac{3}{4}$ " iron pipes at the NE and SE corners of the W  $\frac{1}{2}$  of SW  $\frac{1}{4}$  of SE  $\frac{1}{4}$  of Sec. 25.

COMMENTS: Although the found SE  $\frac{1}{16}$  cor. Sec. 25 and the E  $\frac{1}{16}$  cor. bet. Secs. 25 and 36 do not fit their calculated positions within accepted tolerances, I elected to use them for property line control because of their having been used for boundary control for a long period of time.

The only record I found for these Brass Caps are a set of field notes proported to be original notes, poorly done and not very explicit, kept in the vault at the Bureau of Indian Affairs office at Mission.

R-185-A