

Q-280-A1

N.W. Despain

Ave.

Mon.

755

Lead plug in R.H. Curb.

cross



Patton

37' New Boundary Line - 90'

Project to N. Line of N.W. 3rd St.

Metal Point set in concrete - 1' below

7034

Lead plug

Hamley

Res.

32

Metal point in 6" Conc. Cone 6" Below Ground.

61' M/L

R.A. = 460

N. 56° 32' E.

Wade's Addition.

NE 1/4 NE 1/4 173

Shafer

550

Plat showing  
 Location of New property  
 boundary line in unplatted  
 area lying between North line  
 of Wade's Addition, and the  
 south line of N.W. DeSpain Ave.,  
 City of Pendleton, Ore.  
 Surveyed, staked and platted - 7/12, 1949  
 By W. E. O. Criger.  
 Scale: 1 inch = 30 Feet.

orig

Q-280-A1



W. E. O. CRIGER  
CONSULTING ENGINEER

Memorandum of Field notes on survey for  
Shafer, Kupers and Hamley - N.W. DeSpain

I set up on the monument at the intersection  
of the  $\frac{1}{2}$  of N.W. Furnish ave. and N. Main Streets.  
Projected the  $\frac{1}{2}$  of N.W. Furnish to the intersection  
of N.W. Third St., then projected the  $\frac{1}{2}$  of N.W. 3rd  
Street to the north line of Section 10 T.2 N., R.32  
E.W.M., thence ran westerly on the N. line of sec. 10,  
30 ft to the point of beginning, to establish a new  
line for the purpose of a property division.  
I then ran the division line due south 188 ft,  
to an intersection with the N. line of Wade's  
addition; said point being  $S. 56^{\circ} 32' W. 550$  ft. from  
a point where the west line of N.W. 3rd Street, projected  
southerly would intersect the northerly line of  
Wade's Addition.