

Field Notes

Date: July 18, 1955

Weather: Warm Clear

Firm: Wall & Tenneson
Consulting Engineers

Subject: Private Survey for
Russel Blackler, Real
Estate Agent, Milton
Freewater.

Location: SW $\frac{1}{4}$, SE $\frac{1}{4}$ section
26, Twn 4 N, R37EWM

Chief of Party: Stanley Wallulis
Instrumentman: Donald Branton

We were instructed to survey out a tract of land with the corners established by a prior survey and set by individual land owners. We rough chained and found the points shown on the section line. We established line over the easterly 640.71' of the section line shown.

We then occupied a corner on the section line a distance of 849.32' ~~from~~ the East from the 1/4 corner ~~at~~ on the south line of Sec 26 Twn 4N R37EWM Umatilla ~~Co~~ County, Oregon &

thence: N 2° 01' 30" W - 330¹³ fd. I.P.

S 89° 56' 30" E - 92⁵⁹ fd. Conc. Mon.

S 71° 56' 30" E - 103⁸⁷ fd. Conc Mon

S 71° 56' 30" E - 10⁰³ fd. ~~Conc~~ I.P.

~~S 57° 09' 30" E~~ 57° 09' 30" E - 298⁷¹ fd I.P.

S 89° 42' 30" W - 17²⁵ set I.P

S 89° 42' 30" W - 104⁰⁰ fd. I.P.

S 89° 42' 30" W - 104³⁵ fd I.P.

See also attached drawing Stanley & Hallulis