



619



SCALE 1"=200'

C. H. Storms & Associates

CONSULTING ENGINEERS — ARCHITECTS

304 DENNY BUILDING TELEPHONE 4170 WALLA WALLA, WASH.

- Mechanical
- Structural
- Hydraulic
- Sanitary
- Designs
- Land Surveys
- House Plans
- Blue Prints
- Estimates

A SURVEY FOR  
 H. R. DETER  
 SECTION 15 T. 4 N. R. 28 E.  
 HERMISTON S.W. 1/4 NW 1/4 OREGON

Date FEB. 4 1948  
 Drawn By B.F.C.  
 Checked By G.M.N.

750  
 SHEET OF

Q-1339-AX

15CB

Q-1339-AX  
 619

*no repro avail.*



City Planning  
Supervision  
Valuation  
Surveying  
Reports  
Designs

# C. H. Storms & Associates

CONSULTING ENGINEERS

REGISTERED WASHINGTON, OREGON

C. H. STORMS  
Phone 4692-W

G. M. NEWBILL  
Phone 2982-M

GEO. LAUBACK  
B. F. CHAPMAN  
J. O. BICKFORD, Jr.  
E. BUCKNER

TELEPHONE 4170  
304 Denny Building  
WALLA WALLA, WASH.

FILE

## FIELD NOTES

OWNER: H. R. Deter & Mr. Ellingston

TYPE OF SURVEY: Tract

LOCATION: Section 15, Township 4 North, Range 28 EWM

From a railroad spike set in the Butter Creek Road marking the Southwest corner of Section 15, Township 4 North, Range 28 EWM, I measured North along the West line of said Section 15. At 1320 feet, I found a fence running West. At 3960 feet, I found another fence running West. AT 5280 feet as shown on the original government survey field notes, I set a temporary point for the Northwest corner of said Section 15. I then checked the distance from said point to an existing fence at the North line of the SW $\frac{1}{4}$ SW $\frac{1}{4}$ SW $\frac{1}{4}$  of Section 10, Township 4 North, Range 28 EWM and found this distance to be 660.0 feet.

From a 1" galvanized iron pipe marking the Northeast corner of Section 15, Township 4 North, Range 28 EWM, I measured East along the North line of said Section 15 to the center of an existing road and found this distance to be 2640 feet. AT 3960 feet, I found existing fences running both North and South, and at 5280 feet as shown on the field notes for County Road #610, I set a 1" iron pipe marking the Northwest corner of said Section 15, 0.65 feet West of the temporary corner mentioned above. From

COMPLETE ENGINEERING SERVICE

Q-1339-Ax



-2- FIELD NOTES FOR H. R. DETER & MR. ELLINGSTON

the Northwest corner of said Section 15, I ran on a true line between said corner and the Southwest corner of said Section and set  $5/8$ " iron pins at the  $1/16$  corners and the  $1/4$  corner on the West line of said Section 15. From the above corners, I made the surveys as shown on the accompanying plats.

*Geul N. Storme*

Q-1339-A8