

FIELD NOTES

Revised Field Notes for Section 1, T.4 N., R. 28 E. W.M.

Resurveyed May 1950
By V.R. Fraley #183

The following notes are necessary due to the fact that I used a wrong corner for the N.W. corner of Section 11, T. 4 N., R 28 E. in my first survey of Section 1. in 1949.

On South Line Sec. 2, T. 4 N., R. 28 E

Established line between a 5/8" Iron Pin which is the Sec. corner common to Sec's 2-3-10-11 and a 1" I.P which is the South $\frac{1}{4}$ cor. of Sec. 2. Produced this line on a true bearing of S.89°-27'E a distance of 5295.1 to an intersection with the east line of Sec. 11 which I established in 1949. I set a 2" Galv. I.P. for the Sec. cor common to Sec's 1-2-11-12.

On South line of Sec. 1

From the Sec. Cor. 1-2-11-12 I ran on a true bearing of S.89°-20'E

2659.5 Set a 3/4" I.P. for the South $\frac{1}{4}$ corner of Sec. 1.

References: Power P. bears N.W. Nail 46.3
T.Pole bears S.W. Nail 51.1

5319.0 6"x6"x12" Stone the Sec. corner common to Sec's 1-6-12-13

References: U.S. Reclamation B.M. Moq. bears N.45°E. Dist. 52.6
Oak fence post bears S.45°E. 33'

On West line of Section 1

From the corner 1-2-11-12 I ran on a true bearing of N.0°-21'E

2663.0 Set 1 1/8" I.P. for the West $\frac{1}{4}$ corner of Sec. 1. (This corner I proved correct by running line through on the true east and west Quarter line of Sec. 2.)

5509.7 The N.W. corner of Section 1 which I set in 1949.

On E.& West Quarter line of Sec. 1

On true bearing of S.89°-16'E. from the West $\frac{1}{4}$ cor.

2662.9 Set a 1 1/8" I.P. for the center of the section. (At an intersection with the N & South Quarter line which I est. in 1949.)

5325.8 The East $\frac{1}{4}$ corner of Sec. 1. 3/4" I.P.

North 0°-25'E from center of section

1336.4 I set a 3/4" I.P. for the N.E. corner of the S.W. $\frac{1}{4}$ of the N.E. $\frac{1}{4}$ computing proportionate measurement with the Original Gov't Notes which gave a distance of 1320 ft.

Q-1347-A*

FIELD NOTES

For Tracts of Land in the Lot 3 of Block A of Vickers Addition
To Hermiston, Umatilla County, Ore.

By: Verl R. Fraley

Reg. Land Surveyor No. 183.

Found all the corners of Lot 3 Block A in Vickers Addition from
which I surveyed and marked with iron pipes the tracts of land as
shown on the accompanying map.

Q-1347-AX