



• denotes set 3/8" x 30" iron pin with aluminum cap stamped PLS 933
 □ denotes find stone as noted and set fence post with Co. Surveyor sign

NARRATIVE:

The purpose of this survey was to establish the corners of a 5 acre parcel as recorded in Book 294, Page 148 of the Umatilla County Deed Records.
 We found a stone marked 1/4 in a rock mound on an open hillside as the East one-quarter corner of Section 24, T18, R32E and found a stone marked 3/4 on East face set in a stone mound as the West one-quarter of Section 19, T18, R33E.
 These stones were also found by Staebler in 1968, so by using these stones to establish the range line and the legal description coming from the West one-quarter of Section 19, we set the property corners.

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon		Scale <i>1" = 30'</i>	Dwn. By <i>MCD</i>	Eng. No. <i>85-460</i>	Revision 1
		Date <i>8-20-85</i>	Ctr. P. <i>DMA</i>	No. <i>85-115</i>	Revision 2
Survey for HORN		<i>David H. Krumbein</i>		RECEIVED BY Umatilla County Surveyor Date: <i>10-14-85</i> Rec'd by: <i>K.T.</i> No. <i>25-132-B</i>	
Section 19, T18, R33E, W.M.					