



Curve Data
 1. r = 321.54
 a = 70.36
 t = 35.32
 ch = 70.23
 S13°32'07"W

NARRATIVE:

The purpose of this survey was to establish the boundaries of a parcel of land being purchased by Byrnes Oil Company in Sections 8 and 9, T15, R32E, W.M.

The East and West boundary lines are defined on Roll 9, Pages 582-586 of the Deed Records of Umatilla County, Oregon and are property lines of a parcel belonging to Union Pacific Land Resources Corp. They are defined as being 175.0 feet and 150.00 feet respectively from the main track of the Pilot Rock Branch of the Oregon-Washington Railroad & Navigation Company.

The North and South lines were previously established by our firm in a survey for Pine Lam Inc. and are at points agreed to by the parties involved.

The section line between Sections 8 and 9 is established between the quarter corner to the North and the section corner to the South both of which are 2 inch iron pipes. These points have been used many times before, Umatilla County Surveyor Drawing Nos. 82-48-B, G-850-A, B-11-A and others.

The bearing of the section line of South 0°21'23" East is based upon the legal description on Roll 9, Pages 582-586.

- o denotes find 3/8" iron pin set by this firm for Pine Lam
- o denotes find 2" iron pipe

K E L CR	KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon		Scale 1" = 50' Date 2-18-86	Drn. By MLD Ckd. By DHS	Drng. No. 86-05C Job No. 86-18	Revision 1 5-11-86 Revision 2
	Survey for BYRNES OIL COMPANY in NE1/4, SE1/4 of Sec 8 & NW1/4, SW1/4, Sec 9, T15, R32E, W.M.		REGISTERED PROFESSIONAL LAND SURVEYOR David W. Krumbain		RECEIVED BY Umatilla County Surveyor Date 6-5-86 Rec'd By RA No. 86-53-B	