


SURVEY FOR
 KENNETH & BETTY PROCK
 NW¼ OF NE¼ OF SECTION 32 T.6N., R.35E.W.M.

Scale 1" = 400'



Sept. 24, 1991
 930 Home St.
 Walla Walla, Wa. 99362

NARRATIVE

1. Found railroad spike as used in my survey for Terry Childers in 1973; County No. I-089-AX. Also found by Krumbein in Hendricks survey in 1979 County No. Q-1200-B.
2. Found 1 ½" pipe as used in Terry Childers Survey in 1973 County NO. I-089-B
3. Found ¾" pipe as set in Terry Childers survey in 1973 County NO. I-089-AX. Also used by Krumbein in 1979 survey for Hendricks County No. Q-1200-B.
4. Found ½" reinforcing steel as used in Terry Childers survey in 1973 County No. I-089-AX and Hendricks survey in 1979 County No. Q-1200-B.
5. Set 2" X 3' pipe tagged L.S. 1341
6. Set ¾" X 28" pipe tagged L.S. 1341
7. Split measured distances along East Section line, North-South Centerline and North Section line between found monuments. S.E. corner NW ¼ of NE ¼ set at split of measured distance between 1/16 corners. Distance compared to distance recorded by Krumbein in Hendricks Survey Q-1200-B along the East-West center line of Section. North - South split of quarter section was checked to confirm location of center intersection.

RECEIVED BY
 Umatilla County Surveyor
 Date 6-92
 Rec'd by RF
 No. 92-1018