

S20 S21
S29 S28

Found basalt stone 18x10x5".

(N89°40'46"E 5294.13')
(S89°40'46"W 5293.99')

S21 S22
S28 S27

Found brass cap in mound of stone.

(89°59'47")
(89°59'44")

TOWNSHIP 1 NORTH
RANGE 35 EAST

BASIS OF BEARINGS

The bearings are based on the North Line of Section 28 as per survey F-24-Ax.

NARRATIVE OF SURVEY

This survey was performed at the request of Mr. Larry Eades. The purpose of the survey was to confirm the location and identity of the monument at the southwest corner of Section 21.

In 1969, Mr. Don Staebler identified this corner and said that the stone agreed with the bearing trees in the S.W. and N.W. quadrants. The tamarack in the northwest quad is now dead and down while the fir in the southwest quad has rotted down to just a layer of decayed wood under the leaves. There is presently a live red fir, 34" DBH, approximately 2.5 feet north of the corner stone. This fir tree has an old location poster nailed on its north side. The remains of old fences (see the corner certificate) at the corner indicate that the corner may have been on the north side of the tree but are inconclusive as they have completely settled into the ground.

While the found stone was not the record dimensions, it is at the record bearing and distance from the tamarack bearing tree which still has visible scribing. I confirmed the location of the stone against the survey by Mr. Staebler by tying to the monuments from that survey as shown. I set a brass cap at the position of the stone and nailed a bearing object sign to the south side of the live fir tree. I did not scribe this tree, for the location of the bearing objects set see the filed corner certificate.

(N00°19'01"W 4650.20')
(S0°18'56"E 4649.63')

LEGEND

- SET 2 1/4" BRASS CAP ON A 1 1/8" x 30" GALVANIZED IRON PIPE AT POINT OF FOUND ORIGINAL STONE.
- FOUND 5/8" REBAR ON C/L POWERLINE R/W FROM R2
- ⊕ FOUND BRASS CAP FROM 83-190-R
- R1 CURPIN & NOLAND GLO SPECIAL CONTRACT DATED MAY 4, 1987
- R2 COUNTY SURVEY F-24-Ax
- R3 CORNER CERTIFICATE 83-190-R
- (xxx) RECORD DATA FROM F-24-Ax

This rebar was reported as on the centerline of the powerline right of way on survey F-24-Ax. I did not confirm that information.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Stephen K. Haddock

OREGON
JULY 9, 2001
STEPHEN K. HADDOCK
RENEWS 6-30-09

RECEIVED BY
Umatilla County Surveyor
Date: 2-08
Rec'd By: SK
No.: 08-043-6

SURVEY FOR Mr. Larry Eades 430 Christiansen Loop Rd. Hermiston, OR 97838		PROJECT DATE: November 8, 2007	
		Project No. 07-31	SCALE: 1" = 50'
LOCATION: Section 21, T1N, R35E, W.M., Umatilla County, Oregon.		WITNESS TREE SURVEYING	
		Stephen K. Haddock, PLS P.O. Box 6 Pilot Rock, Oregon 97868 (541) 443-2922	