



Section 27, T.4N.R.27 E.W.M.

LEGEND

- ⊙ Indicates Monuments Found, G.L.D. Brass Cap
- ⊙ Indicates Monuments Set, 36"x2" I.P. with Brass Cap
- ⊙ Indicates 1/2" I.P. Set.

DEPENDENT RESURVEY

This Plat of the resurvey of a portion of Section 27, T.4N.R.27 E.W.M. delineates a retracement and reestablishment of the lines of the original Survey as shown upon the plat approved June 23, 1875, in their true original position according to the best available evidence of the position of the original corners. All Bearings shown are derived from a Solar Observation by me, on Sept. 10, 1963.

SOLAR OBSERVATION
 Date: Sept. 10, 1963
 Standard time: 10:06'08" AM
 Declination: N. 5°00'54"
 Refr. & Para: - 0°00'51"
 Latitude: N. 45°47"
 Horiz. Angle: 37°31'20"
 Vert. Angle: 42°54'30"

I, the undersigned, do hereby certify that the survey shown hereon is true and accurate.

REGISTERED
 OREGON
 LAND SURVEYOR
 Ralph P. Thompson
 MAY 13 1960
 RALPH P. THOMPSON
 509

SURVEY FOR
 STAFFORD HANSELL
 Sec. 27, T.4N.R.27 E.W.M.
 Date: 12-21-63 Scale: 1" = 400'
 R. P. THOMPSON 604
 REGISTERED PROFESSIONAL LAND SURVEYOR
 135 E. COURT AVE. PENDELTON, OREGON

Original
 549-B
 402726-36