

SECTION 13
T. 5 N., R. 29 E. W. M.

EASTERN OREGON
ENGINEERING SERVICE

311 SE COURT AVE. PENDLETON, OREGON

DRWN BY	GKD BY	DATE	DRWG. NO.
			CE-24420-B

2-1270-B

STRANIX AND OFNER
ENGINEERS
PENDLETON, OREGON

PHONE 492

June 23, 1949

Mr. Frank B. Hayes
County Engineer
Umatilla County
Pendleton, Oregon

Dear Sir:

The following is an abstract of the field notes of a survey made to establish the Boundaries of section 13, T.5 N., R.29 E., W.M. The survey was completed last November and the notes should have been filed within 60 days. However, more work was anticipated which did not materialize which explains the delay.

A careful search was made for all corners and $1/4$ corners. At the NW cor. found a 1" iron pipe driven beside the remains of a charred stake in a fence corner. Accepted this and set a concrete monument. At the West $1/4$ corner found a 2" galvanized pipe driven beside the remains of an old stake. Accepted this and set a concrete monument. At the SW corner found an old stake in a mound of rocks. Set a concrete monument. Failed to find the South $1/4$ corner, the SE corner, the East $1/4$ corner. Found the NE corner, the original stake in a mound of rocks. Failed to find the North $1/4$ corner.


From the NE corner, ran a random line south $1\frac{1}{2}$ miles and after a long search found an old stake. Proceeded south another $\frac{1}{2}$ mile and searched for the SE corner of section 24 but failed to find same. Accepted the old stake found as the east $1/4$ corner of section 24 and corrected the random line. Made the distance from the NE corner of section 13 to the east $1/4$ corner of section 24 to be 7945.5 feet. Set the SE corner on line ~~5297.0~~ 5297.0 feet south of the NE corner. Set a concrete Monument. At the mid-point between the NE and the SE corners established the East $1/4$ corner. Set a spike in rock outcrop.

The set the North and South $1/4$ corners on line between the section corners. Set concrete monuments.

To establish the east and west lines of the land lying north of the north line of section 13, i.e. lots 5, 6, 7 and 8 in section 12 the east and west lines of section 13 were produced north to the Columbia River. A concrete monument was set on the east line.

Dimensions are shown on the accompanying map.

Very truly yours,
STRANIX AND OFNER, ENGINEERS


J. T. Stranix