

NARRATIVE OF SURVEY

Location of Survey - The parcel surveyed lies within the S.E. $\frac{1}{4}$ of Section 32, Township 4 North, Range 38 East, W.M., Umatilla County.

Method and Procedure - This survey was performed for Pacific Northwest Bell Telephone Company. The survey involved staking out a site for a proposed Repeater.

We located brass capped iron pipes monumenting the Center $\frac{1}{4}$ corner and the East $\frac{1}{4}$ corner of Section 32 and surveyed by random closed traverse between them. We laid out the proposed repeater site as shown on the map of survey and tied the repeater site to the Center $\frac{1}{4}$ and East $\frac{1}{4}$ Corner of Section 32.

The centerline and right-of-way of State Highway No. 204 is not monumented through this area. For this reason, railroad spikes were set at the visual centerline of State Highway No. 204. These railroad spikes are set only as line reference points for the East and West lines of the Repeater Site and are not on the actual centerline of State Highway No. 204.

The bearings shown on the map of survey are based on the bearing from the brass capped iron pipe monumenting the Center $\frac{1}{4}$ Corner of Section 32 to the brass capped iron pipe monumenting the East $\frac{1}{4}$ Corner of Section 32 being North 89° 55' 32" East as per Staebler Survey No. I-156.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

William R. Wells

William R. Wells, PLS
P.O. Box 398
Pendleton, Oregon 97801
May 20, 1980