

NARRATIVE OF SURVEY

The purpose of this survey was to locate and monument a mutually acceptable boundary line between the lands of Boise Cascade Corporation and the lands of Wallulis and Wells, et al. The boundary line agreement is approximately 2 1/4 miles in length. Approximately 3/4 mile of the boundary line is located along the East line of Section 32, Township 1 North, Range 35 East, W.M. and along the West line of Section 4, Township 1 South, Range 35 East, W.M. Brass capped iron pipe monuments set for the West one-quarter and Northwest Corner of Section 4 and the East one-quarter of Section 32 were referenced with bearing trees and "Certified Record of Land Corner Monumentation" forms were recorded in the Office of the Umatilla County Surveyor. Unless otherwise noted, other monuments were located to denote the common boundary line and are not intended to represent corners of aliquot parts of the sections. The survey was performed using one-second theodolite and infra-red distance measuring equipment.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
  
Willie R. Wells  
  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106



LEGEND

- SET 3/8" X 3/4" I. PIN WITH PLASTIC CAP MARKED "WALLULIS & ASSOC. INC." UNLESS OTHERWISE NOTED.
- MONUMENTS FOUND AS NOTED.
- BEARINGS ARE TRUE BASED ON SOLAR OBSERVATION.
- (OO) - INDICATES BEARINGS AND DISTANCES OF RECORD.



DRAWING: W. Wells Umatilla County Surveyor Date: 6/13/83 1 of 1 SHEET 1 OF 1	TITLE:	SCALE: 1" = 500'	PROJECT:	WALLULIS PROJECT NO:
	REVISIONS:	DATE: 6-13-83	SURVEY OF BOISE CASCADE - WALLULIS & WELLS BOUNDARY LINE AGREEMENT	AGENCY PROJECT NO:
	DES BY: WRW	DR BY: WRW	LOCATED IN SECTION 32, TWP 1 NORTH RGE 35 EAST & SECTION 4, TWP 1 SOUTH RGE 35 EAST, W.M. UMATILLA COUNTY, OREGON	
	CK BY: SWW	PENDLETON, OREGON 97801 503-276-1598		